

A blue decorative shape in the top right corner, consisting of a rectangle with a curved left edge tapering to a point.

Appendix K

DRAINAGE STUDY

A thin green curved line in the bottom right corner, starting from the left and curving upwards and to the right.

**CEQA PRELIMINARY HYDROLOGY/
DRAINAGE STUDY
California Crossings, TM 21046**

County of San Diego, CA
November 2009

Prepared For:

Otay Mesa Crossing, LLC
c/o Erwin Bucy
Regency Centers
915 Wilshire Boulevard, Suite 2200
Los Angeles, CA 90017

Prepared By:



PROJECT DESIGN CONSULTANTS

Planning | Landscape Architecture | Environmental | Engineering | Survey

701 B Street, Suite 800
San Diego, CA 92101
619.235.6471 Tel
619.234.0349 Fax

PDC Job No. 3315.00



Prepared by: C. Pack, P.E.
Under the supervision of

Debby Reece

Debby Reece, PE RCE 56148
Registration Expires 12/31/10

TABLE OF CONTENTS

1. INTRODUCTION	1
2. EXISTING AND PROPOSED DRAINAGE PATTERNS AND IMPROVEMENTS.....	2
3. HYDROLOGIC CRITERIA, METHODOLOGY, AND RESULTS.....	3
3.1 Hydrology Criteria.....	3
3.2 Hydrologic Methodology.....	4
3.3 Description of Hydrologic Modeling Software	4
4. HYDROLOGY ANALYSIS RESULTS	5
4.1 Detention Volume Estimates	5
4.2 Detention Basin Maintenance Summary	6
5. ENVIRONMENTAL IMPACTS.....	6
6. CONCLUSION.....	8

FIGURES

Figure 1: Project Vicinity Map	2
--------------------------------------	---

TABLES

Table 1: Hydrology Criteria.....	3
Table 2: Hydrology Results	5
Table 3: Detention Basin Summary	6

APPENDICES

1	Supporting Documentation (Isopluvial Maps, Runoff Coefficients, etc.)
2	Existing Conditions – Excerpts From Caltrans Report & Drainage Plans
3	Proposed Conditions Rational Method Computer Output
4	Preliminary Detention Calculations
5	Drainage Exhibits
	A – Developed Conditions Hydrology Map

1. INTRODUCTION

This drainage report has been prepared in support of a Tentative Parcel Map and Major Use Permit submittal for the California Crossings project, which is located in the County of San Diego, California. The purpose of this report is to determine the hydrologic impact, if any, to the existing storm drain facilities or natural drainage, and to provide peak 100-year discharge values for existing and proposed conditions.

The drainage analyses presented herein reflect a Tentative Parcel Map and Major Use Permit level-of-effort, which include peak 100-year storm event hydrologic analyses using preliminary grades. Hydraulic analyses for detention, inlets, pipe inverts and HGL's will be provided during final engineering. *Therefore, the purpose of this report submittal is to acquire from the County: 1) concept approval of the proposed storm drain layout, 2) approval of the methodology used in the evaluation of the Project storm drain system hydrology, and 3) identification of critical path drainage issues that need to be addressed during final engineering.*

This project has a gross acreage of 29.6 acres, and is located North of Highway 905 (Otay Mesa Road) and West of Harvest Road and East of State Route 125. The project involves the construction of a retail commercial center and associated parking lots. See Figure 1 for the project vicinity map.




Figure 1: Project Vicinity Map

2. EXISTING AND PROPOSED DRAINAGE PATTERNS AND IMPROVEMENTS

Under existing conditions, the project area currently consists of flat terrain sloping in the south westerly direction, with natural ground cover. Some offsite area along the North and East sides of the project contribute runoff to the site, particularly because the current condition of Harvest Road is not improved and therefore does not function as a drainage divide. Drainage along the

west side of the project is collected in a concrete ditch and directed to the south. A precast double 6'x2' (1.8x0.6m) RCB recently built per the Caltrans plans collects the runoff in the southwest corner of the site and conveys it to the south underneath Otay Mesa Road. A very small portion of the northwest corner of the site drains to the north in the ditch built per the Caltrans plans.

Under proposed conditions, the project grading will be designed to drain to the southwest corner of the site to match existing conditions. The site will provide onsite detention to ensure that runoff resulting from the developed condition is equal to or less than the runoff from the existing condition in order to discharge into the existing double 6'x2' (1.8x0.6m) RCB. In the proposed condition, the offsite runoff east of Harvest Road will be collected by a storm drain extension in Otay Mesa Road so that the offsite water will still drain to the existing culvert.

3. HYDROLOGIC CRITERIA, METHODOLOGY, AND RESULTS

This section of the report summarizes the drainage criteria that were used in the hydrologic analysis and key elements of the methodology.

3.1 Hydrology Criteria

The drainage basins were delineated using available topography and the preliminary proposed grading layout for the project. Table 1 summarizes the key hydrology assumptions and criteria used for the hydrologic modeling.

Table 1: Hydrology Criteria

Hydrology:	100-year storm frequency
Flood Control Detention:	100-year, 6-hour storm event
Soil Type:	Hydrologic Soil Group D
Land Use / Runoff Coefficients:	Based on criteria presented in the 2003 County of San Diego Hydrology Manual.
Rainfall intensity:	Based on intensity duration frequency relationships presented in the 2003 County of San Diego Hydrology Manual.

3.2 Hydrologic Methodology

Hydrology calculations were completed only for proposed conditions as site runoff is conveyed to the existing backbone system. The existing condition for the site was analyzed previously by Caltrans for the adjacent State Route 125 improvements. Excerpts from the *Addendum to the Drainage Report for SR-125 South Toll Road Segment 1A* and the Drainage Plans are provided in Appendix 2 for reference. The drainage addendum was written by Rick Engineering for Caltrans. Caltrans designed the precast double 6'x2' (1.8x0.6m) RCB to convey the existing condition 100-year peak flow from the site and adjacent runoff areas.

For the proposed condition hydrology, the drainage areas were defined according to the preliminary grading concept for the site. Precise grading of the site during final engineering may alter the tributary drainage areas to the individual grass swales, but will not drastically alter the drainage plan for the site.

The area to the East and North of the project is planned for development by others, but it is unknown at this time how the other developer will connect into the backbone system. Therefore, the drainage calculations for this project are based on the existing condition for the offsite runoff areas.

3.3 Description of Hydrologic Modeling Software

The Modified Rational Method was used to determine the 100-year storm flow for the design of the storm system. The Civil-D Rational Method Program was used to perform the hydrologic calculations. This section provides a brief explanation of the computational procedure used in the computer model.

The Civil-D Modified Rational Method Hydrology Program is a computer-aided design program where the user develops a node link model of the watershed. Developing independent node link models for each interior watershed and linking these sub-models together at confluence points creates the node link model. The intensity-duration-frequency relationships are applied to each of the drainage areas in the model to get the peak flow rates at each point of interest.

4. HYDROLOGY ANALYSIS RESULTS

For results of the analysis see Exhibit A for the proposed conditions hydrology map, and Appendices 2 and 3 for existing and proposed conditions hydrology calculations.

The project site's overall proposed drainage basin is the same as the existing conditions. Any increase in storm water runoff generated by the development will be attenuated by a proposed underground detention basin. The hydrology results for the existing and proposed conditions are summarized below.

Table 2: Hydrology Results

	“BACKBONE” (Q ALLOWABLE) EXISTING CONDITIONS PER CALTRANS REPORT			PROPOSED CONDITIONS			
<u><i>Point of Interest (Description)</i></u>	<u><i>Description</i></u>	<u><i>Q100 (cfs)</i></u>	<u><i>Contrib. Area (acres)</i></u>	<u><i>System</i></u>	<u><i>Node</i></u>	<u><i>Q100 (cfs)</i></u>	<u><i>Contrib. Area (acres)</i></u>
Backbone storm drain, double 6'x2' (1.8x0.6m) RCB near Otay Mesa Road	(From “TA1-Watershed A - Summary of Peak Discharge” table in Caltrans Report)	95.3	60.33	System 100	180	Qin=80.7 (undetained), Qout<=25.3 (detained)	19.89
Total at outfall=		95.3	60.33	System 200	285	70.0	40.81
						<=95.3	60.70

4.1 Detention Volume Estimates

The results in Table 2 are dependent on sufficient detention volumes to attenuate the proposed peak flows so that the results are less than or equal to pre-development peak flow rates. The detention basin routing and design of the outlet structures will be performed during final engineering. However, detention volume estimates are needed at this preliminary stage to verify the project has sufficient detention volume. For this reason, Haestad Method's PondPack

software was used to determine the detention volume required to attenuate the peak flow down to the required rate. Refer to Appendix 4 for the calculations.

For all of the area draining into the detention basin (System 100), the peak inflow hydrograph was generated with Rick Engineering Rational Method Hydrograph Generator. This program develops a synthetic hydrograph per the 2003 County Hydrology Manual by using the results of the CivilD output. The inflow hydrograph was then input into PondPack and the curvilinear estimate was used to determine the volume required to attenuate the flow down to the target rate. The target rate is the difference between the backbone peak flow rate and the peak flow rate from System 200 (which represents all of the area that will not drain into the detention basin.) Table 3 summarizes the detention volumes required and detention volumes provided per the tentative parcel map.

Table 3: Detention Basin Summary

<u>Location of Detention Basin</u>	<u>Drainage System</u>	<u>Detention Volume Required</u>	<u>Volume Provided</u>	<u>Notes:</u>
Underground Storage	System 100	1.0 AF	1.2 AF	Assume 5' deep of water storage

4.2 Detention Basin Maintenance Summary

The maintenance of the private underground detention basin facility will be the responsibility of the Property Management Association for the California Crossings project. The detention facility will be designed during final engineering. The provision for maintenance will include a combination of manhole(s) and strategically located inspection port(s) to observe the condition of the facility from the surface. The level of sediment and debris should be inspected at least twice a year. If upon visual inspection, it is found that the outlet is clogged or that sediment or debris has accumulated up to a certain pre-determined depth (i.e., 3 inches), a clean-out should be performed with a vacuum truck, JetVac process, or equally effective method.

5. ENVIRONMENTAL IMPACTS

This section summarizes the following questions for CEQA purposes.

Would the project:

1. **Substantially alter the existing drainage pattern of the site or area, including through the alteration of the course of a stream or river, in a manner which would result in substantial erosion or siltation on- or off-site?**

The project's drainage patterns mimic the existing conditions, so no substantial impacts will exist.

2. **Substantially alter the existing drainage pattern of the site or area, including through the alteration of the course of a stream or river, or substantially increase the rate or amount of surface runoff in a manner which would result in flooding on- or off-site?**

A flood-control underground detention basin will be provided to ensure that peak flow rates under proposed conditions are not greater than existing peak flow rates.

3. **Create or contribute runoff water which would exceed the capacity of existing or planned storm water drainage systems?**

The recently constructed Caltrans culvert crossing underneath Otay Mesa Road was sized for the existing flow rate. Since the detention basin will attenuate back to the Caltrans flow rate for existing conditions, the capacity will not be exceeded.

4. **Place housing within a 100-year flood hazard area as mapped on a federal Flood Hazard Boundary or Flood Insurance Rate Map or other flood hazard delineation map, including County Floodplain Maps? For example; research the foregoing and provide same (to indicate applicability or not) in the study.**

There is no housing proposed for this site. In any case, there are no 100-year flood hazard zones within the project site. See a copy of the FIRM panel in Appendix 1.

5. **Place within a 100-year flood hazard area structures which would impede or redirect flood flows?**

See response to Question 4.

6. **Expose people or structures to a significant risk of loss, injury or death involving flooding, including flooding as a result of the failure of a levee or dam on-site or off site?**

There are no dams or levees within or near the project site.

6. CONCLUSION

This drainage report has been prepared in support of the preliminary design of the storm drain improvements for the tentative parcel map for the California Crossings project. The purpose of this report is to provide peak discharges for use in designing the private storm drain system for the project and to verify that the detention volume provided is adequate to detain the post-project flows to the pre-project flows. The hydrology results indicate that the peak flow from the developed site will be less than the existing flows with the detention basin provided. Therefore, the storm drain system will be sufficient to satisfy County criteria in the post-development condition. A Storm Water Management Plan, submitted separately, describes proposed water quality alternatives to meet BMP requirements.

APPENDIX 1

Supporting Documentation

(Isopluvial Maps, Runoff Coefficients, etc.)



APPROXIMATE SCALE IN FEET

500
0
500

NATIONAL FLOOD INSURANCE PROGRAM

FIRM
FLOOD INSURANCE RATE MAP
**SAN DIEGO COUNTY,
CALIFORNIA AND
INCORPORATED AREAS**

PANEL 2179 OF 2375
(SEE MAP INDEX FOR PANELS NOT PRINTED)


CONTAINS COMMUNITY	NUMBER	PANEL	SUFFIX
SAN DIEGO COUNTY UNINCORPORATED AREAS	062784	2179	F
SAN DIEGO CITY OF	063296	2179	F


MAP NUMBER
06073C2179 F
EFFECTIVE DATE:
JUNE 19, 1997



Federal Emergency Management Agency

This is an official copy of a portion of the above referenced flood map. It was extracted using F-MIT On-Line. This map does not reflect changes or amendments which may have been made subsequent to the date on the title block. For the latest product information about National Flood Insurance Program flood maps check the FEMA Flood Map Store at www.msc.fema.gov





**Table 3-1
RUNOFF COEFFICIENTS FOR URBAN AREAS**

Land Use		Runoff Coefficient "C"					
NRCS Elements	County Elements	% IMPER.	Soil Type				
			A	B	C	D	
Undisturbed Natural Terrain (Natural)	Permanent Open Space	0*	0.20	0.25	0.30	0.35	
Low Density Residential (LDR)	Residential, 1.0 DU/A or less	10	0.27	0.32	0.36	0.41	
Low Density Residential (LDR)	Residential, 2.0 DU/A or less	20	0.34	0.38	0.42	0.46	
Low Density Residential (LDR)	Residential, 2.9 DU/A or less	25	0.38	0.41	0.45	0.49	
Medium Density Residential (MDR)	Residential, 4.3 DU/A or less	30	0.41	0.45	0.48	0.52	
Medium Density Residential (MDR)	Residential, 7.3 DU/A or less	40	0.48	0.51	0.54	0.57	
Medium Density Residential (MDR)	Residential, 10.9 DU/A or less	45	0.52	0.54	0.57	0.60	
Medium Density Residential (MDR)	Residential, 14.5 DU/A or less	50	0.55	0.58	0.60	0.63	
High Density Residential (HDR)	Residential, 24.0 DU/A or less	65	0.66	0.67	0.69	0.71	
High Density Residential (HDR)	Residential, 43.0 DU/A or less	80	0.76	0.77	0.78	0.79	
Commercial/Industrial (N. Com)	Neighborhood Commercial	80	0.76	0.77	0.78	0.79	
Commercial/Industrial (G. Com)	General Commercial	85	0.80	0.80	0.81	0.82	
Commercial/Industrial (O.P. Com)	Office Professional/Commercial	90	0.83	0.84	0.84	0.85	
Commercial/Industrial (Limited I.)	Limited Industrial	90	0.83	0.84	0.84	0.85	
Commercial/Industrial (General I.)	General Industrial	95	0.87	0.87	0.87	0.87	

*The values associated with 0% impervious may be used for direct calculation of the runoff coefficient as described in Section 3.1.2 (representing the pervious runoff coefficient, Cp, for the soil type), or for areas that will remain undisturbed in perpetuity. Justification must be given that the area will remain natural forever (e.g., the area is located in Cleveland National Forest).

DU/A = dwelling units per acre

NRCS = National Resources Conservation Service

**Table 3-1
RUNOFF COEFFICIENTS FOR URBAN AREAS**

Land Use		Runoff Coefficient "C"					
NRCS Elements	County Elements	% IMPER.	Soil Type				
			A	B	C	D	
Undisturbed Natural Terrain (Natural)	Permanent Open Space	0*	0.20	0.25	0.30	0.35	
Low Density Residential (LDR)	Residential, 1.0 DU/A or less	10	0.27	0.32	0.36	0.41	
Low Density Residential (LDR)	Residential, 2.0 DU/A or less	20	0.34	0.38	0.42	0.46	
Low Density Residential (LDR)	Residential, 2.9 DU/A or less	25	0.38	0.41	0.45	0.49	
Medium Density Residential (MDR)	Residential, 4.3 DU/A or less	30	0.41	0.45	0.48	0.52	
Medium Density Residential (MDR)	Residential, 7.3 DU/A or less	40	0.48	0.51	0.54	0.57	
Medium Density Residential (MDR)	Residential, 10.9 DU/A or less	45	0.52	0.54	0.57	0.60	
Medium Density Residential (MDR)	Residential, 14.5 DU/A or less	50	0.55	0.58	0.60	0.63	
High Density Residential (HDR)	Residential, 24.0 DU/A or less	65	0.66	0.67	0.69	0.71	
High Density Residential (HDR)	Residential, 43.0 DU/A or less	80	0.76	0.77	0.78	0.79	
Commercial/Industrial (N. Com)	Neighborhood Commercial	80	0.76	0.77	0.78	0.79	
Commercial/Industrial (G. Com)	General Commercial	85	0.80	0.80	0.81	0.82	
Commercial/Industrial (O.P. Com)	Office Professional/Commercial	90	0.83	0.84	0.84	0.85	
Commercial/Industrial (Limited I.)	Limited Industrial	90	0.83	0.84	0.84	0.85	
Commercial/Industrial (General I.)	General Industrial	95	0.87	0.87	0.87	0.87	

*The values associated with 0% impervious may be used for direct calculation of the runoff coefficient as described in Section 3.1.2 (representing the pervious runoff coefficient, Cp, for the soil type), or for areas that will remain undisturbed in perpetuity. Justification must be given that the area will remain natural forever (e.g., the area is located in Cleveland National Forest).

DU/A = dwelling units per acre

NRCS = National Resources Conservation Service

County of San Diego Hydrology Manual





Rainfall Isopleths

100 Year Rainfall Event - 6 Hours

..... Isopleth (Inches)



THIS MAP IS PROVIDED WITHOUT WARRANTY OF ANY KIND, EITHER EXPRESS OR IMPLIED, INCLUDING BUT NOT LIMITED TO, WARRANTIES OF MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE. This product may contain information from the SANDAG Regional Information System which cannot be reproduced without the written permission of SANDAG. This product may contain information which has been reproduced with permission granted by various service maps.



County of San Diego Hydrology Manual






Rainfall Isoplethals

100 Year Rainfall Event - 24 Hours



THIS MAP IS PROVIDED WITHOUT WARRANTY OF ANY KIND. THE USER EXPRESSLY ACCEPTS THE LIMITATIONS OF MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE. THE USER SHALL BE RESPONSIBLE FOR OBTAINING ANY NECESSARY PERMITS OR RIGHTS OF WAY. THE USER SHALL BE RESPONSIBLE FOR OBTAINING ANY NECESSARY PERMITS OR RIGHTS OF WAY. THE USER SHALL BE RESPONSIBLE FOR OBTAINING ANY NECESSARY PERMITS OR RIGHTS OF WAY.





Directions for Application:

- (1) From precipitation maps determine 6 hr and 24 hr amounts for the selected frequency. These maps are included in the County Hydrology Manual (10, 50, and 100 yr maps included in the Design and Procedure Manual).
- (2) Adjust 6 hr precipitation (if necessary) so that it is within the range of 45% to 65% of the 24 hr precipitation (not applicable to Desert).
- (3) Plot 6 hr precipitation on the right side of the chart.
- (4) Draw a line through the point parallel to the plotted lines.
- (5) This line is the intensity-duration curve for the location being analyzed.

Application Form:

(a) Selected frequency 100 year

(b) $P_6 = \underline{2.50}$ in., $P_{24} = \underline{5.50}$ in., $\frac{P_{24}}{P_6} = \underline{45\%}$ ⁽²⁾

(c) Adjusted $P_6^{(2)} = \underline{2.50}$ in.

(d) $t_x = \underline{\quad}$ min.

(e) $I = \underline{\quad}$ in./hr.

Note: This chart replaces the Intensity-Duration-Frequency curves used since 1965.

P6	1	1.5	2	2.5	3	3.5	4	4.5	5	5.5	6
Duration	1	1.5	2	2.5	3	3.5	4	4.5	5	5.5	6
5	2.53	3.95	5.27	6.59	7.90	9.22	10.54	11.86	13.17	14.49	15.81
7	2.12	3.18	4.24	5.30	6.36	7.42	8.48	9.54	10.60	11.66	12.72
10	1.88	2.83	3.77	4.71	5.65	6.59	7.53	8.47	9.41	10.35	11.29
15	1.30	1.95	2.59	3.24	3.89	4.54	5.19	5.84	6.49	7.13	7.78
20	1.08	1.62	2.15	2.69	3.23	3.77	4.31	4.85	5.39	5.93	6.46
25	0.93	1.40	1.87	2.33	2.80	3.27	3.73	4.20	4.67	5.13	5.60
30	0.83	1.24	1.66	2.07	2.49	2.90	3.32	3.73	4.15	4.58	4.99
40	0.69	1.03	1.36	1.72	2.07	2.41	2.76	3.10	3.45	3.79	4.13
50	0.60	0.90	1.19	1.49	1.79	2.09	2.39	2.69	2.98	3.28	3.58
60	0.53	0.80	1.08	1.33	1.59	1.86	2.12	2.39	2.65	2.92	3.18
80	0.41	0.61	0.82	1.02	1.23	1.43	1.63	1.84	2.04	2.25	2.45
100	0.34	0.51	0.68	0.85	1.02	1.19	1.36	1.53	1.70	1.87	2.04
150	0.29	0.44	0.59	0.73	0.88	1.03	1.18	1.32	1.47	1.62	1.76
180	0.26	0.39	0.52	0.65	0.78	0.91	1.04	1.18	1.31	1.44	1.57
240	0.22	0.33	0.43	0.54	0.65	0.76	0.87	0.98	1.08	1.19	1.30
300	0.19	0.28	0.38	0.47	0.56	0.66	0.75	0.85	0.94	1.03	1.13
360	0.17	0.25	0.33	0.42	0.50	0.58	0.67	0.75	0.84	0.92	1.00

Intensity-Duration Design Chart - Template

FIGURE

3-1

APPENDIX 2

Existing Conditions – Excerpts From Caltrans Report & Drainage Plans



PROJECT DESIGN CONSULTANTS

PLANNING | LANDSCAPE ARCHITECTURE
ENVIRONMENTAL | ENGINEERING | SURVEY

WWW.PROJECTDESIGN.COM

PROJECT CA Crossings

SUBJECT "Backbone" Drainage Condition

PAGE: 1 OF 1 JOB NO.: 3315

DRAWN BY: _____ DATE: _____

CHECKED BY: _____ DATE: _____

Summary of Drainage Calculations from Caltrans Report

$$\begin{aligned}\text{Watershed TAI} &= 244144 \text{ m}^2 \text{ per exhibit} \\ &= 244144 \text{ m}^2 \left(\frac{\text{ft}^2}{(0.3048 \text{ m})^2} \right) \left(\frac{\text{ac}}{43560 \text{ ft}^2} \right) \\ &= 60.33 \text{ acres}\end{aligned}$$

Q₁₀₀

From Reference in Caltrans Report

95.3 cfs [2.7 cms]

Summary of Peak Discharge Table

101.8 cfs [2.884 cms]

WSPG run; modeled each barrel separately $\frac{Q}{\text{barrel}} = 1.442 \text{ cms}$

96.6 cfs [2.735 cms]

FHWA Nomograph for culvert inlet control

→ Not sure why Qs are all slightly different, but we will use the lowest Q (95.3 cfs) in order to be conservative.

DESCRIPTION

This study is an addendum to the Drainage Report for SR-125 South Toll Road Segment 1A and presents a hydrologic and hydraulic analysis for the drainage systems for Otay Mesa Road from Piper Ranch Road to Harvest Road. The following calculations are included in this report: Peak discharge calculations; Culvert inlet and outlet control calculations; Grate inlet calculations; Pipe flow calculations; Bioswale calculations; and Ditch calculations. For design methodologies for these calculations refer to the Drainage Report for SR-125 South Toll Road Segment 1A. The following drainage systems are proposed:


- **System 24:** Includes both off-site and on-site runoff. Off-site runoff is conveyed through pre-cast double box culverts. On-site flows from Otay Mesa Road are collected in inlets and discharged into the box culverts. Flows received from the proposed Sunroad development are also discharged into this system. Water Surface Pressure Gradient Package (WSPGW) is used to analyze the box culverts. System 24 outlets into a grass lined flood control channel designed to convey the 100-year storm event. As the channel depth decreases and meets existing grade, the runoff will follow natural drainage patterns to the southwest, and ultimately drains into an existing drainage channel west of La Media Road.
- **System 25:** Includes both off-site and on-site runoff. Off-site runoff from the infield area between Ramps OM1 and OM4 is conveyed through a single pre-cast box culvert. Additional on-site runoff from Otay Mesa Road and Ramp OM1 are collected in ditches and discharged into the box culvert. Water Surface Pressure Gradient Package (WSPGW) is used to analyze the box culvert. System 25 outlets into the same flood control channel as System 24.
- **System 26:** On-site flows from Otay Mesa Road are discharged through an overside drain and treated with a bioswale.
- **System 27:** Includes on-site runoff from Otay Mesa Road and Ramp OM4 collected in inlets. System 27 is discharged into a flood control channel and combined with flows from Systems 28 and 29 to be treated through a bioswale at the outlet.

LEGEND:



SYSTEM

— WATERSHED BOUNDARY



Summary of Peak Discharge

ID	Peak Discharge (Q_{10})		Peak Discharge (Q_{25})		Peak Discharge (Q_{50})		Peak Discharge (Q_{100})	
	CFS	CMS	CFS	CMS	CFS	CMS	CFS	CMS
TA1 - Watershed A	51.079	1.446	68.105	1.928	88.536	2.507	95.347	2.700
TA2 - System 24h	0.802	0.023	0.997	0.028	1.141	0.032	1.285	0.036
TA3 - System 24m+r	1.632	0.046	2.030	0.057	2.323	0.066	2.616	0.074
TOTAL	53.513	1.515	71.132	2.014	92.001	2.605	99.248	2.810

Notes:

1. To be conservative, it is assumed that discharge from offsite and on-site tributary areas reaches the culvert inlet simultaneously.
2. Peak discharge from watersheds A is calculated based on existing condition. Both City of San Diego and San Diego County require future land developers to detain peak discharge on site.
3. *Within the watershed A, a portion of the tributary area will be developed and will become Sunroad Tech Center. Therefore, some runoff will be conveyed through a 36" RCP to System 24. However, the total discharge of the system 24 remains same at the very downstream since the future development will limit the discharge to existing flow rate through storm water detention.*
4. Based on the information provided by Stevens Cresto Engineering Inc., the discharge of 10-year, 25-year and 100-year flood from the 36" RCP is:
 $Q_{10}=0.44$ cms; $Q_{25}=0.56$ cms, $Q_{100}=0.74$ cms.

T1 Otay Mesa Road double box- west of 2 boxes (no lateral); total Q= 1.442 cms 1
 T2 starting wsel= 159.956 (from downstream channel run)
 T3 J-144648 04/02/07

SO	1000.000	159.572	1		159.956	
R	1094.764	160.044	1	.013		.000
WE	1094.764	160.044	2	.500		.000 0
SH	1094.764	160.044	2		160.044	
CD	1	3	0	.000	.600	1.830 .000 .000 .00
CD	2	1	0	.000	10.000	10.000 .000 .000 .00
Q				1.442	.0	

Program Package Serial Number: 1462

WATER SURFACE PROFILE LISTING

Date:

4- 4-2007 Time:10:41:27

Otay Mesa Road double box- west of 2 boxes (no lateral); total Q= 1.442 cm
starting wsel= 159.956 (from downstream channel run)
J-14464s 04/02/07

Top Height	Invert	Depth	Water	Q	Vel	Vel	Energy	Super	Critical	Flow		
Station	Base Wt	No Wth	Elev	(M3/S)	(M/S)	Head	Grd.El.	Elev	Depth	Width	Dia.-	
M or I.D.	ZL	Prs/Pip										
- -	- -	- -	- -	- -	- -	- -	- -	- -	- -	- -	- -	- -
L/Elem	Ch Slope					SF Ave	HF	SE Dpth	Froude N	Norm Dp	"N"	
X-Fall	ZR	Type Ch										

1000.000	159.572	.359	159.931	1.442	2.20	.25	160.18	.00	.40	1.83	.600	
1.830	0 .0	- -	- -	- -	- -	- -	- -	- -	- -	- -	- -	
- -	- -	- -	- -	- -	- -	- -	- -	- -	- -	- -	- -	
65.586	.0050					.0050	.33	.36	1.17	.36	.013	
.00	BOX											
1065.586	159.899	.359	160.257	1.442	2.20	.25	160.50	.00	.40	1.83	.600	
1.830	0 .0	- -	- -	- -	- -	- -	- -	- -	- -	- -	- -	
- -	- -	- -	- -	- -	- -	- -	- -	- -	- -	- -	- -	
17.602	.0050					.0049	.09	.36	1.17	.36	.013	
.00	BOX											
1083.188	159.986	.361	160.348	1.442	2.18	.24	160.59	.00	.40	1.83	.600	
1.830	0 .0	- -	- -	- -	- -	- -	- -	- -	- -	- -	- -	
- -	- -	- -	- -	- -	- -	- -	- -	- -	- -	- -	- -	

[illegible]

Double box Culvert (Sys 24)

$$\frac{HW}{D} = 1.11$$


$$\therefore HW = 1.11 \times 1.968$$

$$= 2.18'$$

$$= \underline{0.67m}$$



CHART 8



HEADWATER DEPTH
 FOR BOX CULVERTS
 WITH INLET CONTROL

BUREAU OF PUBLIC ROADS JAN. 1963


$$100 = 2.735 \text{ cms} = 96.6 \text{ cfs}$$

$$D = 0.6m = \underline{1.968'}$$

Considering 2 boxes as one

$$\therefore \frac{Q}{B} = \frac{2.735}{1.8 \times 2} = 0.76 \text{ m}^2/\text{s} = \underline{8.18 \text{ ft}^2/\text{s}}$$

STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION		DESIGN OVERSIGHT		RAMON MARTINEZ		CHECKED BY		DATE		DATE REVISD BY		DATE REVISD	
ISSUE RECORD		PURPOSE		DATE		RELEASD FOR CONSTRUCTION		DATE		RELEASD		DATE	
1		1		1		1		1		1		1	



ALL DIMENSIONS ARE IN METERS UNLESS OTHERWISE SHOWN	
THIS PLAN ACCURATE FOR DRAINAGE WORK ONLY	

DRAINAGE PLAN

SCALE 1:500

D-2

DIST	COUNTY	ROUTE	KILOMETER POST TOTAL PROJECT	SHEET NO.	TOTAL SHEETS
11	SD	125	2.7/8.2		

REGISTERED CIVIL ENGINEER DATE XXXXXX

PLANS APPROVAL DATE

California Transportation Ventures, Inc.
5800 Main Drive
Chula Vista, CA 91914

Rick Engineering Company
5820 Friars Road
San Diego, CA 92110

The State of California or the officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.

Caltrans now has a web site! To get to the web site, go to the URL: <http://www.dgs.gov>

DATE PLOTTED => 29-APR-2007
TIME PLOTTED => 14112
04-25-07

ISSUE RECORD	
NO.	PURPOSE
1	RELEASED FOR CONSTRUCTION (INR C-041)
2	XXXXXX

DIST	COUNTY	ROUTE	KILOMETER POST TOTAL PROJECT	SHEET NO.	TOTAL SHEETS
11	SD	125	2.7/8.2		

EA CAMERINO
No. 58844
Exp. 6-30-07
REGISTERED CIVIL ENGINEER

XXXXXX
REGISTERED CIVIL ENGINEER DATE


PLANS APPROVAL DATE

California Transportation Ventures, Inc.
880 Kuhn Drive
Chula Vista, CA 91814


Rick Engineering Company
5620 Friars Road
San Diego, CA 92110

The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.

Caltrans now has a web site To get to the web site, go to <http://www.dot.ca.gov>



SAN DIEGO COUNTY



24

DRAINAGE PLAN

SCALE 1:500

ALL DIMENSIONS ARE IN METERS UNLESS OTHERWISE SHOWN

THIS PLAN ACCURATE FOR DRAINAGE WORK ONLY.

D-3

Caltrans

etric

11

SD

125

2.7/8.2

11

SD

125

2.7/8.2

REGISTERED CIVIL ENGINEER DATE

XXXXXX

REGISTERED CIVIL ENGINEER DATE

XXXXXX

PLANS APPROVAL DATE

XXXXXX

PLANS APPROVAL DATE

XXXXXX

California Transportation Ventures, Inc.

880 Kuhn Drive

Chula Vista, CA 91914

5620 Friars Road

San Diego, CA 92110

EA CAMERINO

No. 58844

Exp. 6-30-07

CIVIL

STATE OF CALIFORNIA

Caltrans now has a web site To get to the web site go to <http://www.dcd.ca.gov>

DRAINAGE SYSTEM

24

(a) DROP STRUCTURE / STILLING BASIN. SEE DD-37.

(b) BOX CULVERT WINGWALLS, H=1.08, m=3.297, $\theta=35^\circ$.

(c) 1.8 m x 0.6 m x 94.45 PRECAST DOUBLE

(d) RCB CULVERT, SEE DD-37 TO DD-39

(e) 600 mm x 28.9 APC (TYPE A)

(f) 600 mm x 26.8 APC (TYPE A)

BOX CULVERT WINGWALLS, H=2.081, m=5.696, $\theta=15^\circ$.

MOD GDO INLET, H=1.15, SEE DD-35

RSR BACKING No. 2, SEE DD-37

4M GRATED-LINE DRAIN WITH REMOVABLE GRATES

27.815 LT

OM 12+05.115

24.767 LT

OM 12+03.922

2.650 LT

OM 12+05.115

250 mm STEEL HR GAS

2760-KP (TO BE RELOCATED)

380 mm PVG SEWER (BY OTHERS)

600 mm APC WATER

300 mm APC WATER (ABANDONED)

FL 160.891

FL 160.017

FL 160.043

FL 159.919

FL 159.914

FL 157.500


OG

FG

OG

FG

IDENTICAL POINT



DRAINAGE PROFILE
SCALE 1:100
DP-82

ALL DIMENSIONS ARE IN METERS UNLESS OTHERWISE SHOWN

DESIGNED BY	DATE	REVISD BY	DATE	CHECKED BY	DATE	REVISD BY	DATE
RAMON MARTINEZ							
DESIGN OVERSIGHT							
DEPARTMENT OF TRANSPORTATION							
STATE OF CALIFORNIA							
Issue	No.	Purpose	Date	Released for Const.	Released for Const.	Released for Const.	Released for Const.
1	1	1	1	1	1	1	1

APPENDIX 3

Proposed Conditions Rational Method Computer Output

San Diego County Rational Hydrology Program

CIVILCADD/CIVILDESIGN Engineering Software, (c)1991-2004 Version 7.4

Rational method hydrology program based on
San Diego County Flood Control Division 2003 hydrology manual
Rational Hydrology Study Date: 03/20/08

PDC JOB 3315 CALIFORNIA CROSSINGS
ONSITE 100 YEAR FLOWS
SYSTEM 100
PROPOSED CONDITIONS, FILE: S100P100

***** Hydrology Study Control Information *****

Program License Serial Number 4049

Rational hydrology study storm event year is 100.0
English (in-lb) input data Units used

Map data precipitation entered:
6 hour, precipitation(inches) = 2.500
24 hour precipitation(inches) = 5.500
P6/P24 = 45.5%
San Diego hydrology manual 'C' values used

Process from Point/Station 100.000 to Point/Station 100.000
**** INITIAL AREA EVALUATION ****

Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 0.000
Decimal fraction soil group D = 1.000
[INDUSTRIAL area type]
(General Industrial)
Impervious value, Ai = 0.950
Sub-Area C Value = 0.870
Initial subarea total flow distance = 100.000(Ft.)
Highest elevation = 545.000(Ft.)
Lowest elevation = 544.000(Ft.)
Elevation difference = 1.000(Ft.) Slope = 1.000 %
USER ENTRY OF INITIAL AREA TIME OF CONCENTRATION
Time of Concentration = 5.00 minutes
Rainfall intensity (I) = 6.587(In/Hr) for a 100.0 year storm
Effective runoff coefficient used for area (Q=KCIA) is C = 0.870
Subarea runoff = 15.931(CFS)
Total initial stream area = 2.780(Ac.)

Process from Point/Station 100.000 to Point/Station 117.000
**** PIPEFLOW TRAVEL TIME (Program estimated size) ****

Upstream point/station elevation = 550.900(Ft.)
Downstream point/station elevation = 539.800(Ft.)
Pipe length = 487.00(Ft.) Manning's N = 0.013
No. of pipes = 1 Required pipe flow = 15.931(CFS)
Nearest computed pipe diameter = 21.00(In.)
Calculated individual pipe flow = 15.931(CFS)
Normal flow depth in pipe = 12.53(In.)
Flow top width inside pipe = 20.60(In.)
Critical Depth = 17.67(In.)
Pipe flow velocity = 10.64(Ft/s)
Travel time through pipe = 0.76 min.
Time of concentration (TC) = 5.76 min.

Process from Point/Station 110.000 to Point/Station 117.000
**** CONFLUENCE OF MINOR STREAMS ****

Along Main Stream number: 1 in normal stream number 1
Stream flow area = 2.780(Ac.)
Runoff from this stream = 15.931(CFS)

Time of concentration = 5.76 min.
Rainfall intensity = 6.011(In/Hr)

Process from Point/Station 105.000 to Point/Station 117.000
**** INITIAL AREA EVALUATION ****

Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 0.000
Decimal fraction soil group D = 1.000
[INDUSTRIAL area type]
(General Industrial)
Impervious value, Ai = 0.950
Sub-Area C Value = 0.870
Initial subarea total flow distance = 775.000(Ft.)
Highest elevation = 555.000(Ft.)
Lowest elevation = 543.800(Ft.)
Elevation difference = 11.200(Ft.) Slope = 1.445 %
INITIAL AREA TIME OF CONCENTRATION CALCULATIONS:
The maximum overland flow distance is 60.00 (Ft)
for the top area slope value of 1.45 %, in a development type of
General Industrial
In Accordance With Figure 3-3
Initial Area Time of Concentration = 2.83 minutes
 $TC = [1.8 * (1.1 - C) * \text{distance}(\text{Ft.})^{.5}] / (\% \text{ slope}^{(1/3)})]$
 $TC = [1.8 * (1.1 - 0.8700) * (60.000^{.5})] / (1.450^{(1/3)}) = 2.83$
The initial area total distance of 775.00 (Ft.) entered leaves a
remaining distance of 715.00 (Ft.)
Using Figure 3-4, the travel time for this distance is 6.28 minutes
for a distance of 715.00 (Ft.) and a slope of 1.45 %
with an elevation difference of 10.37(Ft.) from the end of the top area
 $Tt = [11.9 * \text{length}(\text{Mi})^3] / (\text{elevation change}(\text{Ft.}))^{.385} * 60(\text{min/hr})$
 $= 6.285 \text{ Minutes}$
 $Tt = [(11.9 * 0.1354^3) / (10.37)]^{.385} = 6.28$
Total initial area Ti = 2.83 minutes from Figure 3-3 formula plus
6.28 minutes from the Figure 3-4 formula = 9.12 minutes
Rainfall intensity (I) = 4.471(In/Hr) for a 100.0 year storm
Effective runoff coefficient used for area (Q=KCIA) is C = 0.870
Subarea runoff = 10.191(CFS)
Total initial stream area = 2.620(Ac.)

Process from Point/Station 105.000 to Point/Station 117.000
**** CONFLUENCE OF MINOR STREAMS ****

Along Main Stream number: 1 in normal stream number 2
Stream flow area = 2.620(Ac.)
Runoff from this stream = 10.191(CFS)
Time of concentration = 9.12 min.
Rainfall intensity = 4.471(In/Hr)

Process from Point/Station 112.000 to Point/Station 113.000
**** INITIAL AREA EVALUATION ****

Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 0.000
Decimal fraction soil group D = 1.000
[INDUSTRIAL area type]
(General Industrial)
Impervious value, Ai = 0.950
Sub-Area C Value = 0.870
Initial subarea total flow distance = 151.000(Ft.)
Highest elevation = 551.100(Ft.)
Lowest elevation = 548.900(Ft.)
Elevation difference = 2.200(Ft.) Slope = 1.457 %
USER ENTRY OF INITIAL AREA TIME OF CONCENTRATION
Time of Concentration = 5.00 minutes
Rainfall intensity (I) = 6.587(In/Hr) for a 100.0 year storm
Effective runoff coefficient used for area (Q=KCIA) is C = 0.870
Subarea runoff = 4.642(CFS)
Total initial stream area = 0.810(Ac.)

Process from Point/Station 113.000 to Point/Station 114.000

**** IMPROVED CHANNEL TRAVEL TIME ****

Upstream point elevation = 548.900(Ft.)
 Downstream point elevation = 543.000(Ft.)
 Channel length thru subarea = 215.500(Ft.)
 Channel base width = 20.000(Ft.)
 Slope or 'Z' of left channel bank = 10.000
 Slope or 'Z' of right channel bank = 10.000
 Estimated mean flow rate at midpoint of channel = 6.549(CFS)
 Manning's 'N' = 0.015
 Maximum depth of channel = 1.000(Ft.)
 Flow(q) thru subarea = 6.549(CFS)
 Depth of flow = 0.095(Ft.); Average velocity = 3.304(Ft/s)
 Channel flow top width = 21.893(Ft.)
 Flow Velocity = 3.30(Ft/s)
 Travel time = 1.09 min.
 Time of concentration = 6.09 min.
 Critical depth = 0.146(Ft.)
 Adding area flow to channel
 Decimal fraction soil group A = 0.000
 Decimal fraction soil group B = 0.000
 Decimal fraction soil group C = 0.000
 Decimal fraction soil group D = 1.000
 [INDUSTRIAL area type]
 (General Industrial)
 Impervious value, Ai = 0.950
 Sub-Area C Value = 0.870
 Rainfall intensity = 5.802(In/Hr) for a 100.0 year storm
 Effective runoff coefficient used for total area
 (Q=KCIA) is C = 0.870 CA = 1.444
 Subarea runoff = 3.737(CFS) for 0.850(Ac.)
 Total runoff = 8.379(CFS) Total area = 1.660(Ac.)
 Depth of flow = 0.110(Ft.); Average velocity = 3.627(Ft/s)
 Critical depth = 0.172(Ft.)

 Process from Point/Station 113.000 to Point/Station 115.000
 **** PIPEFLOW TRAVEL TIME (Program estimated size) ****

Upstream point/station elevation = 543.000(Ft.)
 Downstream point/station elevation = 541.400(Ft.)
 Pipe length = 272.00(Ft.) Manning's N = 0.013
 No. of pipes = 1 Required pipe flow = 8.379(CFS)
 Nearest computed pipe diameter = 21.00(In.)
 Calculated individual pipe flow = 8.379(CFS)
 Normal flow depth in pipe = 12.82(In.)
 Flow top width inside pipe = 20.48(In.)
 Critical Depth = 12.90(In.)
 Pipe flow velocity = 5.45(Ft/s)
 Travel time through pipe = 0.83 min.
 Time of concentration (TC) = 6.92 min.

 Process from Point/Station 115.000 to Point/Station 115.000
 **** SUBAREA FLOW ADDITION ****

Decimal fraction soil group A = 0.000
 Decimal fraction soil group B = 0.000
 Decimal fraction soil group C = 0.000
 Decimal fraction soil group D = 1.000
 [INDUSTRIAL area type]
 (General Industrial)
 Impervious value, Ai = 0.950
 Sub-Area C Value = 0.870
 Time of concentration = 6.92 min.
 Rainfall intensity = 5.342(In/Hr) for a 100.0 year storm
 Effective runoff coefficient used for total area
 (Q=KCIA) is C = 0.870 CA = 3.645
 Subarea runoff = 11.093(CFS) for 2.530(Ac.)
 Total runoff = 19.472(CFS) Total area = 4.190(Ac.)

 Process from Point/Station 115.000 to Point/Station 117.000
 **** PIPEFLOW TRAVEL TIME (Program estimated size) ****

Upstream point/station elevation = 541.400(Ft.)
 Downstream point/station elevation = 539.800(Ft.)
 Pipe length = 247.00(Ft.) Manning's N = 0.013

No. of pipes = 1 Required pipe flow = 19.472(CFS)
 Nearest computed pipe diameter = 27.00(In.)
 Calculated individual pipe flow = 19.472(CFS)
 Normal flow depth in pipe = 17.95(In.)
 Flow top width inside pipe = 25.49(In.)
 Critical Depth = 18.52(In.)
 Pipe flow velocity = 6.93(Ft/s)
 Travel time through pipe = 0.59 min.
 Time of concentration (TC) = 7.51 min.

 Process from Point/Station 115.000 to Point/Station 117.000
 **** CONFLUENCE OF MINOR STREAMS ****

Along Main Stream number: 1 in normal stream number 3
 Stream flow area = 4.190(Ac.)
 Runoff from this stream = 19.472(CFS)
 Time of concentration = 7.51 min.
 Rainfall intensity = 5.066(In/Hr)
 Summary of stream data:

Stream No.	Flow rate (CFS)	TC (min)	Rainfall Intensity (In/Hr)
1	15.931	5.76	6.011
2	10.191	9.12	4.471
3	19.472	7.51	5.066

Qmax(1) =
 1.000 * 1.000 * 15.931) +
 1.000 * 0.632 * 10.191) +
 1.000 * 0.767 * 19.472) + = 37.308

Qmax(2) =
 0.744 * 1.000 * 15.931) +
 1.000 * 1.000 * 10.191) +
 0.883 * 1.000 * 19.472) + = 39.226

Qmax(3) =
 0.843 * 1.000 * 15.931) +
 1.000 * 0.824 * 10.191) +
 1.000 * 1.000 * 19.472) + = 41.295

Total of 3 streams to confluence:
 Flow rates before confluence point:
 15.931 10.191 19.472
 Maximum flow rates at confluence using above data:
 37.308 39.226 41.295
 Area of streams before confluence:
 2.780 2.620 4.190
 Results of confluence:
 Total flow rate = 41.295(CFS)
 Time of concentration = 7.513 min.
 Effective stream area after confluence = 9.590(Ac.)

 Process from Point/Station 117.000 to Point/Station 120.000
 **** PIPEFLOW TRAVEL TIME (Program estimated size) ****

Upstream point/station elevation = 539.800(Ft.)
 Downstream point/station elevation = 537.500(Ft.)
 Pipe length = 283.00(Ft.) Manning's N = 0.013
 No. of pipes = 1 Required pipe flow = 41.295(CFS)
 Nearest computed pipe diameter = 33.00(In.)
 Calculated individual pipe flow = 41.295(CFS)
 Normal flow depth in pipe = 23.72(In.)
 Flow top width inside pipe = 29.67(In.)
 Critical Depth = 25.63(In.)
 Pipe flow velocity = 9.04(Ft/s)
 Travel time through pipe = 0.52 min.
 Time of concentration (TC) = 8.03 min.

 Process from Point/Station 120.000 to Point/Station 120.000
 **** SUBAREA FLOW ADDITION ****

Decimal fraction soil group A = 0.000
 Decimal fraction soil group B = 0.000
 Decimal fraction soil group C = 0.000
 Decimal fraction soil group D = 1.000

```

[COMMERCIAL area type
(General Commercial )
Impervious value, Ai = 0.850
Sub-Area C Value = 0.820
Time of concentration = 8.03 min.
Rainfall intensity = 4.851(In/Hr) for a 100.0 year storm
Effective runoff coefficient used for total area
(Q=KCIA) is C = 0.865 CA = 9.163
Subarea runoff = 3.154(CFS) for 1.000(Ac.)
Total runoff = 44.449(CFS) Total area = 10.590(Ac.)

```

```

*****
Process from Point/Station 118.000 to Point/Station 120.000
**** SUBAREA FLOW ADDITION ****

```

```

Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 0.000
Decimal fraction soil group D = 1.000
[INDUSTRIAL area type
(General Industrial )
Impervious value, Ai = 0.950
Sub-Area C Value = 0.870
Time of concentration = 8.03 min.
Rainfall intensity = 4.851(In/Hr) for a 100.0 year storm
Effective runoff coefficient used for total area
(Q=KCIA) is C = 0.866 CA = 9.964
Subarea runoff = 3.883(CFS) for 0.920(Ac.)
Total runoff = 48.332(CFS) Total area = 11.510(Ac.)

```

```

*****
Process from Point/Station 120.000 to Point/Station 180.000
**** PIPEFLOW TRAVEL TIME (Program estimated size) ****

```

```

Upstream point/station elevation = 537.500(Ft.)
Downstream point/station elevation = 535.000(Ft.)
Pipe length = 150.00(Ft.) Manning's N = 0.013
No. of pipes = 1 Required pipe flow = 48.332(CFS)
Nearest computed pipe diameter = 30.00(In.)
Calculated individual pipe flow = 48.332(CFS)
Normal flow depth in pipe = 22.50(In.)
Flow top width inside pipe = 25.98(In.)
Critical Depth = 27.33(In.)
Pipe flow velocity = 12.23(Ft/s)
Travel time through pipe = 0.20 min.
Time of concentration (TC) = 8.24 min.

```

```

*****
Process from Point/Station 120.000 to Point/Station 180.000
**** CONFLUENCE OF MAIN STREAMS ****

```

```

The following data inside Main Stream is listed:
In Main Stream number: 1
Stream flow area = 11.510(Ac.)
Runoff from this stream = 48.332(CFS)
Time of concentration = 8.24 min.
Rainfall intensity = 4.773(In/Hr)
Program is now starting with Main Stream No. 2

```

```

*****
Process from Point/Station 150.000 to Point/Station 155.000
**** INITIAL AREA EVALUATION ****

```

```

Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 0.000
Decimal fraction soil group D = 1.000
[INDUSTRIAL area type
(General Industrial )
Impervious value, Ai = 0.950
Sub-Area C Value = 0.870
Initial subarea total flow distance = 338.000(Ft.)
Highest elevation = 542.000(Ft.)
Lowest elevation = 536.500(Ft.)
Elevation difference = 5.500(Ft.) Slope = 1.627 %
INITIAL AREA TIME OF CONCENTRATION CALCULATIONS:
The maximum overland flow distance is 70.00 (Ft)

```

for the top area slope value of 1.63 %, in a development type of
 General Industrial
 In Accordance With Figure 3-3
 Initial Area Time of Concentration = 2.95 minutes
 $TC = [1.8 * (1.1 - C) * distance(Ft.)^{.5}] / (\% \text{ slope}^{(1/3)})$
 $TC = [1.8 * (1.1 - 0.8700) * (70.000^{.5})] / (1.627^{(1/3)}) = 2.95$
 The initial area total distance of 338.00 (Ft.) entered leaves a
 remaining distance of 268.00 (Ft.)
 Using Figure 3-4, the travel time for this distance is 2.82 minutes
 for a distance of 268.00 (Ft.) and a slope of 1.63 %
 with an elevation difference of 4.36(Ft.) from the end of the top area
 $Tt = [11.9 * length(Mi)^3 / (elevation \ change(Ft.))]^{.385} * 60(\text{min/hr})$
 $= 2.824 \text{ Minutes}$
 $Tt = [(11.9 * 0.0508^3) / (4.36)]^{.385} = 2.82$
 Total initial area $Ti = 2.95$ minutes from Figure 3-3 formula plus
 2.82 minutes from the Figure 3-4 formula = 5.77 minutes
 Rainfall intensity (I) = 6.006(In/Hr) for a 100.0 year storm
 Effective runoff coefficient used for area (Q=KCIA) is C = 0.870
 Subarea runoff = 8.152(CFS)
 Total initial stream area = 1.560(Ac.)

 Process from Point/Station 155.000 to Point/Station 160.000
 **** IMPROVED CHANNEL TRAVEL TIME ****

Upstream point elevation = 536.500(Ft.)
 Downstream point elevation = 535.000(Ft.)
 Channel length thru subarea = 160.000(Ft.)
 Channel base width = 5.000(Ft.)
 Slope or 'Z' of left channel bank = 3.000
 Slope or 'Z' of right channel bank = 3.000
 Manning's 'N' = 0.030
 Maximum depth of channel = 1.000(Ft.)
 Flow(q) thru subarea = 8.152(CFS)
 Depth of flow = 0.491(Ft.), Average velocity = 2.568(Ft/s)
 Channel flow top width = 7.943(Ft.)
 Flow Velocity = 2.57(Ft/s)
 Travel time = 1.04 min.
 Time of concentration = 6.81 min.
 Critical depth = 0.398(Ft.)

 Process from Point/Station 157.000 to Point/Station 160.000
 **** SUBAREA FLOW ADDITION ****

Decimal fraction soil group A = 0.000
 Decimal fraction soil group B = 0.000
 Decimal fraction soil group C = 0.000
 Decimal fraction soil group D = 1.000
 [COMMERCIAL area type]
 (General Commercial)
 Impervious value, $A_i = 0.850$
 Sub-Area C Value = 0.820
 Time of concentration = 6.81 min.
 Rainfall intensity = 5.398(In/Hr) for a 100.0 year storm
 Effective runoff coefficient used for total area
 (Q=KCIA) is C = 0.847 CA = 2.481
 Subarea runoff = 5.239(CFS) for 1.370(Ac.)
 Total runoff = 13.390(CFS) Total area = 2.930(Ac.)

 Process from Point/Station 160.000 to Point/Station 165.000
 **** PIPEFLOW TRAVEL TIME (Program estimated size) ****

Upstream point/station elevation = 533.000(Ft.)
 Downstream point/station elevation = 532.000(Ft.)
 Pipe length = 103.00(Ft.) Manning's N = 0.013
 No. of pipes = 1 Required pipe flow = 13.390(CFS)
 Nearest computed pipe diameter = 21.00(In.)
 Calculated individual pipe flow = 13.390(CFS)
 Normal flow depth in pipe = 14.98(In.)
 Flow top width inside pipe = 19.00(In.)
 Critical Depth = 16.34(In.)
 Pipe flow velocity = 7.30(Ft/s)
 Travel time through pipe = 0.24 min.
 Time of concentration (TC) = 7.04 min.

Process from Point/Station 160.000 to Point/Station 165.000
**** CONFLUENCE OF MINOR STREAMS ****

Along Main Stream number: 2 in normal stream number 1
Stream flow area = 2.930(Ac.)
Runoff from this stream = 13.390(CFS)
Time of concentration = 7.04 min.
Rainfall intensity = 5.281(In/Hr)

Process from Point/Station 161.000 to Point/Station 162.000
**** INITIAL AREA EVALUATION ****

Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 0.000
Decimal fraction soil group D = 1.000
[INDUSTRIAL area type]
(General Industrial)
Impervious value, Ai = 0.950
Sub-Area C Value = 0.870
Initial subarea total flow distance = 148.000(Ft.)
Highest elevation = 551.000(Ft.)
Lowest elevation = 548.900(Ft.)
Elevation difference = 2.100(Ft.) Slope = 1.419 %
USER ENTRY OF INITIAL AREA TIME OF CONCENTRATION
Time of Concentration = 5.00 minutes
Rainfall intensity (I) = 6.587(In/Hr) for a 100.0 year storm
Effective runoff coefficient used for area (Q=KCIA) is C = 0.870
Subarea runoff = 1.089(CFS)
Total initial stream area = 0.190(Ac.)

Process from Point/Station 162.000 to Point/Station 165.000
**** IMPROVED CHANNEL TRAVEL TIME ****

Upstream point elevation = 548.900(Ft.)
Downstream point elevation = 535.000(Ft.)
Channel length thru subarea = 674.000(Ft.)
Channel base width = 20.000(Ft.)
Slope or 'Z' of left channel bank = 50.000
Slope or 'Z' of right channel bank = 50.000
Estimated mean flow rate at midpoint of channel = 3.444(CFS)
Manning's 'N' = 0.015
Maximum depth of channel = 1.000(Ft.)
Flow(q) thru subarea = 3.444(CFS)
Depth of flow = 0.068(Ft.), Average velocity = 2.165(Ft/s)
Channel flow top width = 26.798(Ft.)
Flow Velocity = 2.16(Ft/s)
Travel time = 5.19 min.
Time of concentration = 10.19 min.
Critical depth = 0.090(Ft.)
Adding area flow to channel
Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 0.000
Decimal fraction soil group D = 1.000
[INDUSTRIAL area type]
(General Industrial)
Impervious value, Ai = 0.950
Sub-Area C Value = 0.870
Rainfall intensity = 4.162(In/Hr) for a 100.0 year storm
Effective runoff coefficient used for total area
(Q=KCIA) is C = 0.870 CA = 1.375
Subarea runoff = 4.632(CFS) for 1.390(Ac.)
Total runoff = 5.721(CFS) Total area = 1.580(Ac.)
Depth of flow = 0.091(Ft.), Average velocity = 2.567(Ft/s)
Critical depth = 0.123(Ft.)

Process from Point/Station 162.000 to Point/Station 165.000
**** CONFLUENCE OF MINOR STREAMS ****

Along Main Stream number: 2 in normal stream number 2
Stream flow area = 1.580(Ac.)
Runoff from this stream = 5.721(CFS)
Time of concentration = 10.19 min.

Rainfall intensity = 4.162(In/Hr)

Process from Point/Station 163.000 to Point/Station 164.000
**** INITIAL AREA EVALUATION ****

Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 0.000
Decimal fraction soil group D = 1.000
[INDUSTRIAL area type]
(General Industrial)
Impervious value, Ai = 0.950
Sub-Area C Value = 0.870
Initial subarea total flow distance = 460.000(Ft.)
Highest elevation = 543.800(Ft.)
Lowest elevation = 537.900(Ft.)
Elevation difference = 5.900(Ft.) Slope = 1.283 %
INITIAL AREA TIME OF CONCENTRATION CALCULATIONS:
The maximum overland flow distance is 60.00 (Ft)
for the top area slope value of 1.28 %, in a development type of
General Industrial
In Accordance With Figure 3-3
Initial Area Time of Concentration = 2.95 minutes
 $TC = [1.8 * (1.1 - C) * distance(Ft.)^{.5}] / (\% slope^{(1/3)})]$
 $TC = [1.8 * (1.1 - 0.8700) * (60.000^{.5})] / (1.280^{(1/3)}) = 2.95$
The initial area total distance of 460.00 (Ft.) entered leaves a
remaining distance of 400.00 (Ft.)
Using Figure 3-4, the travel time for this distance is 4.22 minutes
for a distance of 400.00 (Ft.) and a slope of 1.28 %
with an elevation difference of 5.12(Ft.) from the end of the top area
 $Tt = [11.9 * length(Mi)^3] / (elevation change(Ft.))^{.385} * 60(min/hr)$
 $= 4.216 Minutes$
 $Tt = [(11.9 * 0.0758^3) / (5.12)]^{.385} = 4.22$
Total initial area Ti = 2.95 minutes from Figure 3-3 formula plus
4.22 minutes from the Figure 3-4 formula = 7.17 minutes
Rainfall intensity (I) = 5.221(In/Hr) for a 100.0 year storm
Effective runoff coefficient used for area (Q=KCIA) is C = 0.870
Subarea runoff = 8.085(CFS)
Total initial stream area = 1.780(Ac.)

Process from Point/Station 164.000 to Point/Station 165.000
**** PIPEFLOW TRAVEL TIME (Program estimated size) ****

Upstream point/station elevation = 534.000(Ft.)
Downstream point/station elevation = 530.000(Ft.)
Pipe length = 104.00(Ft.) Manning's N = 0.013
No. of pipes = 1 Required pipe flow = 8.085(CFS)
Nearest computed pipe diameter = 15.00(In.)
Calculated individual pipe flow = 8.085(CFS)
Normal flow depth in pipe = 8.71(In.)
Flow top width inside pipe = 14.80(In.)
Critical Depth = 13.42(In.)
Pipe flow velocity = 10.95(Ft/s)
Travel time through pipe = 0.16 min.
Time of concentration (TC) = 7.33 min.

Process from Point/Station 164.000 to Point/Station 165.000
**** CONFLUENCE OF MINOR STREAMS ****

Along Main Stream number: 2 in normal stream number 3
Stream flow area = 1.780(Ac.)
Runoff from this stream = 8.085(CFS)
Time of concentration = 7.33 min.
Rainfall intensity = 5.148(In/Hr)
Summary of stream data:

Stream No.	Flow rate (CFS)	TC (min)	Rainfall Intensity (In/Hr)
------------	-----------------	----------	----------------------------

1	13.390	7.04	5.281
2	5.721	10.19	4.162
3	8.085	7.33	5.148

Qmax(1) = 1.000 * 1.000 * 13.390 +

$$1.000 * 0.691 * 5.721) +$$

$$1.000 * 0.961 * 8.085) + = 25.115$$

$$Q_{max}(2) = 0.788 * 1.000 * 13.390) +$$

$$1.000 * 1.000 * 5.721) +$$

$$0.808 * 1.000 * 8.085) + = 22.809$$

$$Q_{max}(3) = 0.975 * 1.000 * 13.390) +$$

$$1.000 * 0.719 * 5.721) +$$

$$1.000 * 1.000 * 8.085) + = 25.251$$

Total of 3 streams to confluence:
 Flow rates before confluence point:
 13.390 5.721 8.085
 Maximum flow rates at confluence using above data:
 25.115 22.809 25.251
 Area of streams before confluence:
 2.930 1.580 1.780
 Results of confluence:
 Total flow rate = 25.251(CFS)
 Time of concentration = 7.328 min.
 Effective stream area after confluence = 6.290 (Ac.)

++++++
 Process from Point/Station 165.000 to Point/Station 180.000
 **** PIPEFLOW TRAVEL TIME (Program estimated size) ****

Upstream point/station elevation = 532.000(Ft.)
 Downstream point/station elevation = 530.000(Ft.)
 Pipe length = 200.00(Ft.) Manning's N = 0.013
 No. of pipes = 1 Required pipe flow = 25.251(CFS)
 Nearest computed pipe diameter = 27.00(In.)
 Calculated individual pipe flow = 25.251(CFS)
 Normal flow depth in pipe = 18.52(In.)
 Flow top width inside pipe = 25.07(In.)
 Critical Depth = 21.07(In.)
 Pipe flow velocity = 8.68(Ft/s)
 Travel time through pipe = 0.38 min.
 Time of concentration (TC) = 7.71 min.

++++++
 Process from Point/Station 165.000 to Point/Station 180.000
 **** CONFLUENCE OF MAIN STREAMS ****

The following data inside Main Stream is listed:
 In Main Stream number: 2
 Stream flow area = 6.290 (Ac.)
 Runoff from this stream = 25.251(CFS)
 Time of concentration = 7.71 min.
 Rainfall intensity = 4.981(In/Hr)
 Program is now starting with Main Stream No. 3

++++++
 Process from Point/Station 170.000 to Point/Station 180.000
 **** INITIAL AREA EVALUATION ****

Decimal fraction soil group A = 0.000
 Decimal fraction soil group B = 0.000
 Decimal fraction soil group C = 0.000
 Decimal fraction soil group D = 1.000
 [COMMERCIAL area type]
 (General Commercial)
 Impervious value, Ai = 0.850
 Sub-Area C Value = 0.820
 Initial subarea total flow distance = 330.000(Ft.)
 Highest elevation = 543.000(Ft.)
 Lowest elevation = 538.000(Ft.)
 Elevation difference = 5.000(Ft.) Slope = 1.515 %
 INITIAL AREA TIME OF CONCENTRATION CALCULATIONS:
 The maximum overland flow distance is 75.00 (Ft)
 for the top area slope value of 1.52 %, in a development type of
 General Commercial
 In Accordance With Figure 3-3
 Initial Area Time of Concentration = 3.80 minutes
 $TC = [1.8 * (1.1 - C) * distance(Ft.)^{.5}] / (\% slope^{(1/3)})$
 $TC = [1.8 * (1.1 - 0.8200) * (75.000^{.5})] / (1.520^{(1/3)}) = 3.80$
 The initial area total distance of 330.00 (Ft.) entered leaves a
 remaining distance of 255.00 (Ft.)

Using Figure 3-4, the travel time for this distance is 2.79 minutes
for a distance of 255.00 (Ft.) and a slope of 1.52 %
with an elevation difference of 3.88(Ft.) from the end of the top area
 $Tt = [11.9 * \text{length}(\text{Mi})^3 / (\text{elevation change}(\text{Ft.}))^{.385} * 60(\text{min/hr})]$
= 2.790 Minutes
 $Tt = [(11.9 * 0.0483^3) / (3.88)]^{.385} = 2.79$
Total initial area $Ti = 3.80$ minutes from Figure 3-3 formula plus
2.79 minutes from the Figure 3-4 formula = 6.59 minutes
Rainfall intensity (I) = 5.514(In/Hr) for a 100.0 year storm
Effective runoff coefficient used for area (Q=KCIA) is $C = 0.820$
Subarea runoff = 9.450(CFS)
Total initial stream area = 2.090(Ac.)

Process from Point/Station 170.000 to Point/Station 180.000
**** CONFLUENCE OF MAIN STREAMS ****

The following data inside Main Stream is listed:

In Main Stream number: 3
Stream flow area = 2.090(Ac.)
Runoff from this stream = 9.450(CFS)
Time of concentration = 6.59 min.
Rainfall intensity = 5.514(In/Hr)
Summary of stream data:

Stream No.	Flow rate (CFS)	TC (min)	Rainfall Intensity (In/Hr)
1	48.332	8.24	4.773
2	25.251	7.71	4.981
3	9.450	6.59	5.514

$Q_{\max}(1) =$
1.000 * 1.000 * 48.332) +
0.958 * 1.000 * 25.251) +
0.866 * 1.000 * 9.450) + = 80.708
 $Q_{\max}(2) =$
1.000 * 0.936 * 48.332) +
1.000 * 1.000 * 25.251) +
0.903 * 1.000 * 9.450) + = 79.026
 $Q_{\max}(3) =$
1.000 * 0.799 * 48.332) +
1.000 * 0.854 * 25.251) +
1.000 * 1.000 * 9.450) + = 69.652

Total of 3 main streams to confluence:

Flow rates before confluence point:

48.332 25.251 9.450

Maximum flow rates at confluence using above data:

80.708 79.026 69.652

Area of streams before confluence:

11.510 6.290 2.090

Results of confluence:

Total flow rate = 80.708(CFS)

Time of concentration = 8.239 min.

Effective stream area after confluence = 19.890(Ac.)

End of computations, total study area = 19.890 (Ac.)

San Diego County Rational Hydrology Program

CIVILCADD/CIVILDESIGN Engineering Software, (c)1991-2004 Version 7.4

Rational method hydrology program based on
San Diego County Flood Control Division 2003 hydrology manual
Rational Hydrology Study Date: 03/20/08

PDC JOB 3315 CALIFORNIA CROSSINGS
PROPOSED CONDITIONS
SYSTEM 200
FILE: S200P100

***** Hydrology Study Control Information *****

Program License Serial Number 4049

Rational hydrology study storm event year is 100.0
English (in-lb) input data Units used

Map data precipitation entered:
6 hour, precipitation(inches) = 2.500
24 hour precipitation(inches) = 5.500
P6/P24 = 45.5%
San Diego hydrology manual 'C' values used

Process from Point/Station 200.000 to Point/Station 205.000
**** INITIAL AREA EVALUATION ****

Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 0.000
Decimal fraction soil group D = 1.000
{UNDISTURBED NATURAL TERRAIN }
(Permanent Open Space)
Impervious value, Ai = 0.000
Sub-Area C Value = 0.350
Initial subarea total flow distance = 893.000(Ft.)
Highest elevation = 596.000(Ft.)
Lowest elevation = 560.000(Ft.)
Elevation difference = 36.000(Ft.) Slope = 4.031 %
INITIAL AREA TIME OF CONCENTRATION CALCULATIONS:
The maximum overland flow distance is 100.00 (Ft)
for the top area slope value of 4.03 %, in a development type of
Permanent Open Space
In Accordance With Figure 3-3
Initial Area Time of Concentration = 8.48 minutes
 $TC = [1.8 * (1.1 - C) * distance(Ft.)^{.5}] / (\% slope^{(1/3)})$
 $TC = [1.8 * (1.1 - 0.3500) * (100.000^{.5})] / (4.030^{(1/3)}) = 8.48$
The initial area total distance of 893.00 (Ft.) entered leaves a
remaining distance of 793.00 (Ft.)
Using Figure 3-4, the travel time for this distance is 4.59 minutes
for a distance of 793.00 (Ft.) and a slope of 4.03 %
with an elevation difference of 31.96(Ft.) from the end of the top area
 $Tt = [11.9 * length(Mi)^3] / (elevation\ change(Ft.))^{.385} * 60(min/hr)$
= 4.592 Minutes
 $Tt = [(11.9 * 0.1502^3) / (31.96)]^{.385} = 4.59$
Total initial area Ti = 8.48 minutes from Figure 3-3 formula plus
4.59 minutes from the Figure 3-4 formula = 13.08 minutes
Rainfall intensity (I) = 3.543(In/Hr) for a 100.0 year storm
Effective runoff coefficient used for area (Q=KCIA) is C = 0.350
Subarea runoff = 8.247(CFS)
Total initial stream area = 6.650(Ac.)

Process from Point/Station 205.000 to Point/Station 215.000
**** PIPEFLOW TRAVEL TIME (Program estimated size) ****

Upstream point/station elevation = 556.000(Ft.)
Downstream point/station elevation = 546.000(Ft.)
Pipe length = 32.00(Ft.) Manning's N = 0.013
No. of pipes = 1 Required pipe flow = 8.247(CFS)
Nearest computed pipe diameter = 9.00(In.)

Calculated individual pipe flow = 8.247(CFS)
Normal flow depth in pipe = 6.62(In.)
Flow top width inside pipe = 7.94(In.)
Critical depth could not be calculated.
Pipe flow velocity = 23.66(Ft/s)
Travel time through pipe = 0.02 min.
Time of concentration (TC) = 13.10 min.

Process from Point/Station 205.000 to Point/Station 215.000
**** CONFLUENCE OF MINOR STREAMS ****

Along Main Stream number: 1 in normal stream number 1
Stream flow area = 6.650(Ac.)
Runoff from this stream = 8.247(CFS)
Time of concentration = 13.10 min.
Rainfall intensity = 3.539(In/Hr)

Process from Point/Station 207.000 to Point/Station 210.000
**** INITIAL AREA EVALUATION ****

Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 0.000
Decimal fraction soil group D = 1.000
[COMMERCIAL area type]
(General Commercial)
Impervious value, Ai = 0.850
Sub-Area C Value = 0.820
Initial subarea total flow distance = 184.000(Ft.)
Highest elevation = 551.500(Ft.)
Lowest elevation = 550.000(Ft.)
Elevation difference = 1.500(Ft.) Slope = 0.815 %
INITIAL AREA TIME OF CONCENTRATION CALCULATIONS:
The maximum overland flow distance is 60.00 (Ft)
for the top area slope value of 0.82 %, in a development type of
General Commercial
In Accordance With Figure 3-3
Initial Area Time of Concentration = 4.17 minutes
 $TC = [1.8 * (1.1 - C) * distance(Ft.)^{.5}] / (\% slope^{(1/3)})]$
 $TC = [1.8 * (1.1 - 0.8200) * (60.000^{.5})] / (0.820^{(1/3)}) = 4.17$
The initial area total distance of 184.00 (Ft.) entered leaves a
remaining distance of 124.00 (Ft.)
Using Figure 3-4, the travel time for this distance is 2.03 minutes
for a distance of 124.00 (Ft.) and a slope of 0.82 %
with an elevation difference of 1.02(Ft.) from the end of the top area
 $Tt = [11.9 * length(Mi)^3] / (elevation change(Ft.))^{.385} * 60(min/hr)$
 $= 2.031 Minutes$
 $Tt = [(11.9 * 0.0235^3) / (1.02)]^{.385} = 2.03$
Total initial area Ti = 4.17 minutes from Figure 3-3 formula plus
2.03 minutes from the Figure 3-4 formula = 6.20 minutes
Rainfall intensity (I) = 5.732(In/Hr) for a 100.0 year storm
Effective runoff coefficient used for area (Q=KCIA) is C = 0.820
Subarea runoff = 9.260(CFS)
Total initial stream area = 1.970(Ac.)

Process from Point/Station 208.000 to Point/Station 210.000
**** SUBAREA FLOW ADDITION ****

Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 0.000
Decimal fraction soil group D = 1.000
[INDUSTRIAL area type]
(General Industrial)
Impervious value, Ai = 0.950
Sub-Area C Value = 0.870
Time of concentration = 6.20 min.
Rainfall intensity = 5.732(In/Hr) for a 100.0 year storm
Effective runoff coefficient used for total area
(Q=KCIA) is C = 0.835 CA = 2.355
Subarea runoff = 4.239(CFS) for 0.850(Ac.)
Total runoff = 13.499(CFS) Total area = 2.820(Ac.)

Process from Point/Station 210.000 to Point/Station 215.000
**** PIPEFLOW TRAVEL TIME (Program estimated size) ****

Upstream point/station elevation = 547.000(Ft.)
Downstream point/station elevation = 546.000(Ft.)
Pipe length = 251.00(Ft.) Manning's N = 0.013
No. of pipes = 1 Required pipe flow = 13.499(CFS)
Nearest computed pipe diameter = 24.00(In.)
Calculated individual pipe flow = 13.499(CFS)
Normal flow depth in pipe = 18.59(In.)
Flow top width inside pipe = 20.06(In.)
Critical Depth = 15.88(In.)
Pipe flow velocity = 5.17(Ft/s)
Travel time through pipe = 0.81 min.
Time of concentration (TC) = 7.01 min.

Process from Point/Station 210.000 to Point/Station 215.000
**** CONFLUENCE OF MINOR STREAMS ****

Along Main Stream number: 1 in normal stream number 2
Stream flow area = 2.820(Ac.)
Runoff from this stream = 13.499(CFS)
Time of concentration = 7.01 min.
Rainfall intensity = 5.296(In/Hr)
Summary of stream data:

Stream No.	Flow rate (CFS)	TC (min)	Rainfall Intensity (In/Hr)
1	8.247	13.10	3.539
2	13.499	7.01	5.296

Qmax(1) =
1.000 * 1.000 * 8.247) +
0.668 * 1.000 * 13.499) + = 17.268

Qmax(2) =
1.000 * 0.535 * 8.247) +
1.000 * 1.000 * 13.499) + = 17.914

Total of 2 streams to confluence:
Flow rates before confluence point:
8.247 13.499
Maximum flow rates at confluence using above data:
17.268 17.914
Area of streams before confluence:
6.650 2.820
Results of confluence:
Total flow rate = 17.914(CFS)
Time of concentration = 7.011 min.
Effective stream area after confluence = 9.470(Ac.)

Process from Point/Station 215.000 to Point/Station 225.000
**** PIPEFLOW TRAVEL TIME (Program estimated size) ****

Upstream point/station elevation = 546.000(Ft.)
Downstream point/station elevation = 544.300(Ft.)
Pipe length = 292.00(Ft.) Manning's N = 0.013
No. of pipes = 1 Required pipe flow = 17.914(CFS)
Nearest computed pipe diameter = 27.00(In.)
Calculated individual pipe flow = 17.914(CFS)
Normal flow depth in pipe = 17.58(In.)
Flow top width inside pipe = 25.74(In.)
Critical Depth = 17.74(In.)
Pipe flow velocity = 6.54(Ft/s)
Travel time through pipe = 0.74 min.
Time of concentration (TC) = 7.76 min.

Process from Point/Station 215.000 to Point/Station 225.000
**** CONFLUENCE OF MINOR STREAMS ****

Along Main Stream number: 1 in normal stream number 1
Stream flow area = 9.470(Ac.)
Runoff from this stream = 17.914(CFS)
Time of concentration = 7.76 min.
Rainfall intensity = 4.963(In/Hr)

 Process from Point/Station 220.000 to Point/Station 225.000
 **** INITIAL AREA EVALUATION ****

Decimal fraction soil group A = 0.000
 Decimal fraction soil group B = 0.000
 Decimal fraction soil group C = 0.000
 Decimal fraction soil group D = 1.000
 [COMMERCIAL area type]
 (General Commercial)
 Impervious value, Ai = 0.850
 Sub-Area C Value = 0.820
 Initial subarea total flow distance = 300.000(Ft.)
 Highest elevation = 551.400(Ft.)
 Lowest elevation = 549.800(Ft.)
 Elevation difference = 1.600(Ft.) Slope = 0.533 %
 INITIAL AREA TIME OF CONCENTRATION CALCULATIONS:
 The maximum overland flow distance is 50.00 (Ft)
 for the top area slope value of 0.53 %, in a development type of
 General Commercial
 In Accordance With Figure 3-3
 Initial Area Time of Concentration = 4.40 minutes
 $TC = [1.8 * (1.1 - C) * distance(Ft.)^{.5}] / (\% slope^{(1/3)})]$
 $TC = [1.8 * (1.1 - 0.8200) * (50.000^{.5})] / (0.530^{(1/3)})] = 4.40$
 The initial area total distance of 300.00 (Ft.) entered leaves a
 remaining distance of 250.00 (Ft.)
 Using Figure 3-4, the travel time for this distance is 4.12 minutes
 for a distance of 250.00 (Ft.) and a slope of 0.53 %
 with an elevation difference of 1.33(Ft.) from the end of the top area
 $Tt = [11.9 * length(Mi)^3] / (elevation change(Ft.))^{.385} * 60(min/hr)$
 $= 4.123 \text{ Minutes}$
 $Tt = ([11.9 * 0.0473^3] / (1.33))^{.385} = 4.12$
 Total initial area Ti = 4.40 minutes from Figure 3-3 formula plus
 4.12 minutes from the Figure 3-4 formula = 8.53 minutes
 Rainfall intensity (I) = 4.668(In/Hr) for a 100.0 year storm
 Effective runoff coefficient used for area (Q=KCIA) is C = 0.820
 Subarea runoff = 3.024(CFS)
 Total initial stream area = 0.790(Ac.)

 Process from Point/Station 222.000 to Point/Station 225.000
 **** SUBAREA FLOW ADDITION ****

Decimal fraction soil group A = 0.000
 Decimal fraction soil group B = 0.000
 Decimal fraction soil group C = 0.000
 Decimal fraction soil group D = 1.000
 [INDUSTRIAL area type]
 (General Industrial)
 Impervious value, Ai = 0.950
 Sub-Area C Value = 0.870
 Time of concentration = 8.53 min.
 Rainfall intensity = 4.668(In/Hr) for a 100.0 year storm
 Effective runoff coefficient used for total area
 (Q=KCIA) is C = 0.851 CA = 1.788
 Subarea runoff = 5.321(CFS) for 1.310(Ac.)
 Total runoff = 8.345(CFS) Total area = 2.100(Ac.)

 Process from Point/Station 225.000 to Point/Station 225.000
 **** CONFLUENCE OF MINOR STREAMS ****

Along Main Stream number: 1 in normal stream number 2
 Stream flow area = 2.100(Ac.)
 Runoff from this stream = 8.345(CFS)
 Time of concentration = 8.53 min.
 Rainfall intensity = 4.668(In/Hr)
 Summary of stream data:

Stream No.	Flow rate (CFS)	TC (min)	Rainfall Intensity (In/Hr)
------------	-----------------	----------	----------------------------

1	17.914	7.76	4.963
2	8.345	8.53	4.668

Qmax(1) = 1.000 * 1.000 * 17.914) +

1.000 * 0.910 * 8.345) + = 25.504
Qmax(2) = 0.941 * 1.000 * 17.914) +
1.000 * 1.000 * 8.345) + = 25.197

Total of 2 streams to confluence:
Flow rates before confluence point:
17.914 8.345
Maximum flow rates at confluence using above data:
25.504 25.197
Area of streams before confluence:
9.470 2.100
Results of confluence:
Total flow rate = 25.504(CFS)
Time of concentration = 7.756 min.
Effective stream area after confluence = 11.570(Ac.)

Process from Point/Station 225.000 to Point/Station 230.000
**** PIPEFLOW TRAVEL TIME (Program estimated size) ****

Upstream point/station elevation = 544.300(Ft.)
Downstream point/station elevation = 541.500(Ft.)
Pipe length = 434.00(Ft.) Manning's N = 0.013
No. of pipes = 1 Required pipe flow = 25.504(CFS)
Nearest computed pipe diameter = 30.00(In.)
Calculated individual pipe flow = 25.504(CFS)
Normal flow depth in pipe = 19.83(In.)
Flow top width inside pipe = 28.40(In.)
Critical Depth = 20.65(In.)
Pipe flow velocity = 7.41(Ft/s)
Travel time through pipe = 0.98 min.
Time of concentration (TC) = 8.73 min.

Process from Point/Station 230.000 to Point/Station 230.000
**** SUBAREA FLOW ADDITION ****

Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 0.000
Decimal fraction soil group D = 1.000
{COMMERCIAL area type }
(General Commercial)
Impervious value, Ai = 0.850
Sub-Area C Value = 0.820
Time of concentration = 8.73 min.
Rainfall intensity = 4.597(In/Hr) for a 100.0 year storm
Effective runoff coefficient used for total area
(Q=KCIA) is C = 0.588 CA = 7.642
Subarea runoff = 9.631(CFS) for 1.430(Ac.)
Total runoff = 35.135(CFS) Total area = 13.000(Ac.)

Process from Point/Station 230.000 to Point/Station 235.000
**** PIPEFLOW TRAVEL TIME (Program estimated size) ****

Upstream point/station elevation = 541.500(Ft.)
Downstream point/station elevation = 541.000(Ft.)
Pipe length = 37.00(Ft.) Manning's N = 0.013
No. of pipes = 1 Required pipe flow = 35.135(CFS)
Nearest computed pipe diameter = 27.00(In.)
Calculated individual pipe flow = 35.135(CFS)
Normal flow depth in pipe = 21.56(In.)
Flow top width inside pipe = 21.66(In.)
Critical Depth = 24.15(In.)
Pipe flow velocity = 10.32(Ft/s)
Travel time through pipe = 0.06 min.
Time of concentration (TC) = 8.79 min.

Process from Point/Station 235.000 to Point/Station 238.000
**** PIPEFLOW TRAVEL TIME (Program estimated size) ****

Upstream point/station elevation = 541.000(Ft.)
Downstream point/station elevation = 540.000(Ft.)
Pipe length = 392.00(Ft.) Manning's N = 0.013

No. of pipes = 1 Required pipe flow = 35.135(CFS)
 Nearest computed pipe diameter = 39.00(In.)
 Calculated individual pipe flow = 35.135(CFS)
 Normal flow depth in pipe = 27.42(In.)
 Flow top width inside pipe = 35.64(In.)
 Critical Depth = 22.58(In.)
 Pipe flow velocity = 5.63(Ft/s)
 Travel time through pipe = 1.16 min.
 Time of concentration (TC) = 9.95 min.

 Process from Point/Station 235.000 to Point/Station 238.000
 **** CONFLUENCE OF MINOR STREAMS ****

Along Main Stream number: 1 in normal stream number 1
 Stream flow area = 13.000(Ac.)
 Runoff from this stream = 35.135(CFS)
 Time of concentration = 9.95 min.
 Rainfall intensity = 4.226(In/Hr)

 Process from Point/Station 236.000 to Point/Station 238.000
 **** INITIAL AREA EVALUATION ****

Decimal fraction soil group A = 0.000
 Decimal fraction soil group B = 0.000
 Decimal fraction soil group C = 0.000
 Decimal fraction soil group D = 1.000
 [INDUSTRIAL area type]
 (General Industrial)
 Impervious value, Ai = 0.950
 Sub-Area C Value = 0.870
 Initial subarea total flow distance = 620.000(Ft.)
 Highest elevation = 576.000(Ft.)
 Lowest elevation = 546.000(Ft.)
 Elevation difference = 30.000(Ft.) Slope = 4.839 %
 INITIAL AREA TIME OF CONCENTRATION CALCULATIONS:
 The maximum overland flow distance is 90.00 (Ft)
 for the top area slope value of 4.84 %, in a development type of
 General Industrial
 In Accordance With Figure 3-3
 Initial Area Time of Concentration = 2.32 minutes
 $TC = [1.8 * (1.1 - C) * \text{distance}(\text{Ft.})^{.5}] / (\% \text{ slope}^{(1/3)})]$
 $TC = [1.8 * (1.1 - 0.8700) * (90.000^{.5})] / (4.840^{(1/3)}) = 2.32$
 The initial area total distance of 620.00 (Ft.) entered leaves a
 remaining distance of 530.00 (Ft.)
 Using Figure 3-4, the travel time for this distance is 3.14 minutes
 for a distance of 530.00 (Ft.) and a slope of 4.84 %
 with an elevation difference of 25.65(Ft.) from the end of the top area
 $Tt = [11.9 * \text{length}(\text{Mi})^3 / (\text{elevation change}(\text{Ft.}))]^{.385} * 60(\text{min/hr})$
 $= 3.138 \text{ Minutes}$
 $Tt = [(11.9 * 0.1004^3) / (25.65)]^{.385} = 3.14$
 Total initial area Ti = 2.32 minutes from Figure 3-3 formula plus
 3.14 minutes from the Figure 3-4 formula = 5.46 minutes
 Rainfall intensity (I) = 6.224(In/Hr) for a 100.0 year storm
 Effective runoff coefficient used for area (Q=KCIA) is C = 0.870
 Subarea runoff = 3.736(CFS)
 Total initial stream area = 0.690(Ac.)

 Process from Point/Station 237.000 to Point/Station 238.000
 **** SUBAREA FLOW ADDITION ****

Decimal fraction soil group A = 0.000
 Decimal fraction soil group B = 0.000
 Decimal fraction soil group C = 0.000
 Decimal fraction soil group D = 1.000
 [INDUSTRIAL area type]
 (General Industrial)
 Impervious value, Ai = 0.950
 Sub-Area C Value = 0.870
 Time of concentration = 5.46 min.
 Rainfall intensity = 6.224(In/Hr) for a 100.0 year storm
 Effective runoff coefficient used for total area
 (Q=KCIA) is C = 0.870 CA = 1.175
 Subarea runoff = 3.574(CFS) for 0.660(Ac.)
 Total runoff = 7.310(CFS) Total area = 1.350(Ac.)

 Process from Point/Station 237.000 to Point/Station 238.000
 **** CONFLUENCE OF MINOR STREAMS ****

Along Main Stream number: 1 in normal stream number 2

Stream flow area = 1.350(Ac.)
 Runoff from this stream = 7.310(CFS)
 Time of concentration = 5.46 min.
 Rainfall intensity = 6.224(In/Hr)
 Summary of stream data:

Stream No.	Flow rate (CFS)	TC (min)	Rainfall Intensity (In/Hr)
------------	-----------------	----------	----------------------------

1	35.135	9.95	4.226
2	7.310	5.46	6.224

Qmax(1) =
 1.000 * 1.000 * 35.135) +
 0.679 * 1.000 * 7.310) + = 40.098

Qmax(2) =
 1.000 * 0.549 * 35.135) +
 1.000 * 1.000 * 7.310) + = 26.587

Total of 2 streams to confluence:
 Flow rates before confluence point:
 35.135 7.310
 Maximum flow rates at confluence using above data:
 40.098 26.587
 Area of streams before confluence:
 13.000 1.350
 Results of confluence:
 Total flow rate = 40.098(CFS)
 Time of concentration = 9.951 min.
 Effective stream area after confluence = 14.350(Ac.)

 Process from Point/Station 238.000 to Point/Station 265.000
 **** PIPEFLOW TRAVEL TIME (Program estimated size) ****

Upstream point/station elevation = 540.000(Ft.)
 Downstream point/station elevation = 539.500(Ft.)
 Pipe length = 91.00(Ft.) Manning's N = 0.013
 No. of pipes = 1 Required pipe flow = 40.098(CFS)
 Nearest computed pipe diameter = 36.00(In.)
 Calculated individual pipe flow = 40.098(CFS)
 Normal flow depth in pipe = 24.61(In.)
 Flow top width inside pipe = 33.49(In.)
 Critical Depth = 24.72(In.)
 Pipe flow velocity = 7.79(Ft/s)
 Travel time through pipe = 0.19 min.
 Time of concentration (TC) = 10.15 min.

 Process from Point/Station 238.000 to Point/Station 265.000
 **** CONFLUENCE OF MINOR STREAMS ****

Along Main Stream number: 1 in normal stream number 1

Stream flow area = 14.350(Ac.)
 Runoff from this stream = 40.098(CFS)
 Time of concentration = 10.15 min.
 Rainfall intensity = 4.173(In/Hr)

 Process from Point/Station 250.000 to Point/Station 255.000
 **** INITIAL AREA EVALUATION ****

Decimal fraction soil group A = 0.000
 Decimal fraction soil group B = 0.000
 Decimal fraction soil group C = 0.000
 Decimal fraction soil group D = 1.000
 [COMMERCIAL area type]
 (General Commercial)
 Impervious value, Ai = 0.850
 Sub-Area C Value = 0.820
 Initial subarea total flow distance = 373.000(Ft.)
 Highest elevation = 551.000(Ft.)

Lowest elevation = 545.000(Ft.)
 Elevation difference = 6.000(Ft.) Slope = 1.609 %
 INITIAL AREA TIME OF CONCENTRATION CALCULATIONS:
 The maximum overland flow distance is 75.00 (Ft)
 for the top area slope value of 1.61 %, in a development type of
 General Commercial
 In Accordance With Figure 3-3
 Initial Area Time of Concentration = 3.72 minutes
 $TC = [1.8 * (1.1 - C) * \text{distance}(\text{Ft.})^{.5}] / (\% \text{ slope}^{(1/3)})$
 $TC = [1.8 * (1.1 - 0.8200) * (75.000^{.5})] / (1.610^{(1/3)}) = 3.72$
 The initial area total distance of 373.00 (Ft.) entered leaves a
 remaining distance of 298.00 (Ft.)
 Using Figure 3-4, the travel time for this distance is 3.08 minutes
 for a distance of 298.00 (Ft.) and a slope of 1.61 %
 with an elevation difference of 4.80(Ft.) from the end of the top area
 $Tt = [11.9 * \text{length}(\text{Mi})^3 / (\text{elevation change}(\text{Ft.}))^{.385}] * 60(\text{min/hr})$
 $= 3.077 \text{ Minutes}$
 $Tt = [(11.9 * 0.0564^3) / (4.80)]^{.385} = 3.08$
 Total initial area $Ti = 3.72$ minutes from Figure 3-3 formula plus
 3.08 minutes from the Figure 3-4 formula = 6.80 minutes
 Rainfall intensity (I) = 5.401(In/Hr) for a 100.0 year storm
 Effective runoff coefficient used for area (Q=KCIA) is $C = 0.820$
 Subarea runoff = 12.756(CFS)
 Total initial stream area = 2.880(Ac.)

 Process from Point/Station 255.000 to Point/Station 260.000
 **** PIPEFLOW TRAVEL TIME (Program estimated size) ****

Upstream point/station elevation = 539.000(Ft.)
 Downstream point/station elevation = 538.000(Ft.)
 Pipe length = 187.00(Ft.) Manning's N = 0.013
 No. of pipes = 1 Required pipe flow = 12.756(CFS)
 Nearest computed pipe diameter = 24.00(In.)
 Calculated individual pipe flow = 12.756(CFS)
 Normal flow depth in pipe = 15.82(In.)
 Flow top width inside pipe = 22.75(In.)
 Critical Depth = 15.41(In.)
 Pipe flow velocity = 5.81(Ft/s)
 Travel time through pipe = 0.54 min.
 Time of concentration (TC) = 7.34 min.

 Process from Point/Station 260.000 to Point/Station 260.000
 **** SUBAREA FLOW ADDITION ****

Decimal fraction soil group A = 0.000
 Decimal fraction soil group B = 0.000
 Decimal fraction soil group C = 0.000
 Decimal fraction soil group D = 1.000
 [COMMERCIAL area type]
 (General Commercial)
 Impervious value, $A_i = 0.850$
 Sub-Area C Value = 0.820
 Time of concentration = 7.34 min.
 Rainfall intensity = 5.143(In/Hr) for a 100.0 year storm
 Effective runoff coefficient used for total area
 (Q=KCIA) is $C = 0.820$ $CA = 2.665$
 Subarea runoff = 0.951(CFS) for 0.370(Ac.)
 Total runoff = 13.707(CFS) Total area = 3.250(Ac.)

 Process from Point/Station 260.000 to Point/Station 265.000
 **** PIPEFLOW TRAVEL TIME (Program estimated size) ****

Upstream point/station elevation = 538.000(Ft.)
 Downstream point/station elevation = 536.000(Ft.)
 Pipe length = 150.00(Ft.) Manning's N = 0.013
 No. of pipes = 1 Required pipe flow = 13.707(CFS)
 Nearest computed pipe diameter = 21.00(In.)
 Calculated individual pipe flow = 13.707(CFS)
 Normal flow depth in pipe = 13.56(In.)
 Flow top width inside pipe = 20.09(In.)
 Critical Depth = 16.52(In.)
 Pipe flow velocity = 8.35(Ft/s)
 Travel time through pipe = 0.30 min.
 Time of concentration (TC) = 7.64 min.

Process from Point/Station 260.000 to Point/Station 265.000
**** CONFLUENCE OF MINOR STREAMS ****

Along Main Stream number: 1 in normal stream number 2

Stream flow area = 3.250(Ac.)
Runoff from this stream = 13.707(CFS)
Time of concentration = 7.64 min.
Rainfall intensity = 5.012(In/Hr)
Summary of stream data:

Stream No.	Flow rate (CFS)	TC (min)	Rainfall Intensity (In/Hr)
------------	-----------------	----------	----------------------------

1	40.098	10.15	4.173
2	13.707	7.64	5.012

Qmax(1) =
1.000 * 1.000 * 40.098) +
0.833 * 1.000 * 13.707) + = 51.511

Qmax(2) =
1.000 * 0.753 * 40.098) +
1.000 * 1.000 * 13.707) + = 43.890

Total of 2 streams to confluence:

Flow rates before confluence point:

40.098 13.707

Maximum flow rates at confluence using above data:

51.511 43.890

Area of streams before confluence:

14.350 3.250

Results of confluence:

Total flow rate = 51.511(CFS)

Time of concentration = 10.146 min.

Effective stream area after confluence = 17.600(Ac.)

Process from Point/Station 265.000 to Point/Station 285.000
**** PIPEFLOW TRAVEL TIME (Program estimated size) ****

Upstream point/station elevation = 536.000(Ft.)
Downstream point/station elevation = 532.000(Ft.)
Pipe length = 480.00(Ft.) Manning's N = 0.013
No. of pipes = 1 Required pipe flow = 51.511(CFS)
Nearest computed pipe diameter = 36.00(In.)
Calculated individual pipe flow = 51.511(CFS)
Normal flow depth in pipe = 25.41(In.)
Flow top width inside pipe = 32.81(In.)
Critical Depth = 28.01(In.)
Pipe flow velocity = 9.66(Ft/s)
Travel time through pipe = 0.83 min.
Time of concentration (TC) = 10.97 min.

Process from Point/Station 265.000 to Point/Station 285.000
**** CONFLUENCE OF MINOR STREAMS ****

Along Main Stream number: 1 in normal stream number 1

Stream flow area = 17.600(Ac.)
Runoff from this stream = 51.511(CFS)
Time of concentration = 10.97 min.
Rainfall intensity = 3.967(In/Hr)

Process from Point/Station 275.000 to Point/Station 280.000
**** INITIAL AREA EVALUATION ****

Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 0.000
Decimal fraction soil group D = 1.000
[UNDISTURBED NATURAL TERRAIN]
(Permanent Open Space)
Impervious value, Ai = 0.000
Sub-Area C Value = 0.350
Initial subarea total flow distance = 788.000(Ft.)
Highest elevation = 616.000(Ft.)

Lowest elevation = 572.000(Ft.)
 Elevation difference = 44.000(Ft.) Slope = 5.584 %
 INITIAL AREA TIME OF CONCENTRATION CALCULATIONS:
 The maximum overland flow distance is 100.00 (Ft)
 for the top area slope value of 5.58 %, in a development type of
 Permanent Open Space
 In Accordance With Figure 3-3
 Initial Area Time of Concentration = 7.61 minutes
 $TC = [1.8 * (1.1 - C) * \text{distance}(\text{Ft.})^{.5}] / (\% \text{ slope}^{(1/3)})]$
 $TC = [1.8 * (1.1 - 0.3500) * (100.000^{.5})] / (5.584^{(1/3)}) = 7.61$
 The initial area total distance of 788.00 (Ft.) entered leaves a
 remaining distance of 688.00 (Ft.)
 Using Figure 3-4, the travel time for this distance is 3.63 minutes
 for a distance of 688.00 (Ft.) and a slope of 5.58 %
 with an elevation difference of 38.42(Ft.) from the end of the top area
 $Tt = [11.9 * \text{length}(\text{Mi})^3 / (\text{elevation change}(\text{Ft.}))^{.385}] * 60(\text{min/hr})$
 $= 3.630 \text{ Minutes}$
 $Tt = [(11.9 * 0.1303^3) / (38.42)]^{.385} = 3.63$
 Total initial area $Ti = 7.61$ minutes from Figure 3-3 formula plus
 3.63 minutes from the Figure 3-4 formula = 11.24 minutes
 Rainfall intensity (I) = 3.906(In/Hr) for a 100.0 year storm
 Effective runoff coefficient used for area (Q=KCIA) is $C = 0.350$
 Subarea runoff = 11.321(CFS)
 Total initial stream area = 8.280(Ac.)

++++++
 Process from Point/Station 280.000 to Point/Station 285.000
 **** IMPROVED CHANNEL TRAVEL TIME ****

Upstream point elevation = 572.000(Ft.)
 Downstream point elevation = 541.000(Ft.)
 Channel length thru subarea = 1219.000(Ft.)
 Channel base width = 20.000(Ft.)
 Slope or 'Z' of left channel bank = 5.000
 Slope or 'Z' of right channel bank = 5.000
 Estimated mean flow rate at midpoint of channel = 16.748(CFS)
 Manning's 'N' = 0.030
 Maximum depth of channel = 1.000(Ft.)
 Flow(q) thru subarea = 16.748(CFS)
 Depth of flow = 0.257(Ft.), Average velocity = 3.064(Ft/s)
 Channel flow top width = 22.568(Ft.)
 Flow Velocity = 3.06(Ft/s)
 Travel time = 6.63 min.
 Time of concentration = 17.87 min.
 Critical depth = 0.273(Ft.)
 Adding area flow to channel
 Decimal fraction soil group A = 0.000
 Decimal fraction soil group B = 0.000
 Decimal fraction soil group C = 0.000
 Decimal fraction soil group D = 1.000
 [UNDISTURBED NATURAL TERRAIN]
 (Permanent Open Space)
 Impervious value, $A_i = 0.000$
 Sub-Area C Value = 0.350
 Rainfall intensity = 2.897(In/Hr) for a 100.0 year storm
 Effective runoff coefficient used for total area
 (Q=KCIA) is $C = 0.350$ $CA = 7.626$
 Subarea runoff = 10.771(CFS) for 13.510(Ac.)
 Total runoff = 22.091(CFS) Total area = 21.790(Ac.)
 Depth of flow = 0.302(Ft.), Average velocity = 3.396(Ft/s)
 Critical depth = 0.328(Ft.)

++++++
 Process from Point/Station 280.000 to Point/Station 285.000
 **** CONFLUENCE OF MINOR STREAMS ****

Along Main Stream number: 1 in normal stream number 2
 Stream flow area = 21.790(Ac.)
 Runoff from this stream = 22.091(CFS)
 Time of concentration = 17.87 min.
 Rainfall intensity = 2.897(In/Hr)

++++++
 Process from Point/Station 281.000 to Point/Station 285.000
 **** INITIAL AREA EVALUATION ****

Decimal fraction soil group A = 0.000
 Decimal fraction soil group B = 0.000

Decimal fraction soil group C = 0.000
 Decimal fraction soil group D = 1.000
 [INDUSTRIAL area type]
 (General Industrial)
 Impervious value, Ai = 0.950
 Sub-Area C Value = 0.870
 Initial subarea total flow distance = 555.000(Ft.)
 Highest elevation = 545.000(Ft.)
 Lowest elevation = 538.000(Ft.)
 Elevation difference = 7.000(Ft.) Slope = 1.261 %
 INITIAL AREA TIME OF CONCENTRATION CALCULATIONS:
 The maximum overland flow distance is 60.00 (Ft)
 for the top area slope value of 1.26 %, in a development type of
 General Industrial
 In Accordance With Figure 3-3
 Initial Area Time of Concentration = 2.97 minutes
 $TC = [1.8 * (1.1 - C) * distance(Ft.)^{.5}] / (\% slope^{(1/3)})]$
 $TC = [1.8 * (1.1 - 0.8700) * (60.000^{.5})] / (1.260^{(1/3)}) = 2.97$
 The initial area total distance of 555.00 (Ft.) entered leaves a
 remaining distance of 495.00 (Ft.)
 Using Figure 3-4, the travel time for this distance is 5.00 minutes
 for a distance of 495.00 (Ft.) and a slope of 1.26 %
 with an elevation difference of 6.24(Ft.) from the end of the top area
 $Tt = [(11.9 * length(Mi)^3) / (elevation change(Ft.))]^{.385} * 60 (min/hr)$
 $= 4.998 \text{ Minutes}$
 $Tt = [(11.9 * 0.0938^3) / (6.24)]^{.385} = 5.00$
 Total initial area Ti = 2.97 minutes from Figure 3-3 formula plus
 5.00 minutes from the Figure 3-4 formula = 7.97 minutes
 Rainfall intensity (I) = 4.877(In/Hr) for a 100.0 year storm
 Effective runoff coefficient used for area (Q=KCIA) is C = 0.870
 Subarea runoff = 2.503(CFS)
 Total initial stream area = 0.590(Ac.)

 Process from Point/Station 282.000 to Point/Station 285.000
 **** SUBAREA FLOW ADDITION ****

Decimal fraction soil group A = 0.000
 Decimal fraction soil group B = 0.000
 Decimal fraction soil group C = 0.000
 Decimal fraction soil group D = 1.000
 [INDUSTRIAL area type]
 (General Industrial)
 Impervious value, Ai = 0.950
 Sub-Area C Value = 0.870
 Time of concentration = 7.97 min.
 Rainfall intensity = 4.877(In/Hr) for a 100.0 year storm
 Effective runoff coefficient used for total area
 (Q=KCIA) is C = 0.870 CA = 1.114
 Subarea runoff = 2.928(CFS) for 0.690(Ac.)
 Total runoff = 5.431(CFS) Total area = 1.280(Ac.)

 Process from Point/Station 282.000 to Point/Station 285.000
 **** CONFLUENCE OF MINOR STREAMS ****

Along Main Stream number: 1 in normal stream number 3
 Stream flow area = 1.280(Ac.)
 Runoff from this stream = 5.431(CFS)
 Time of concentration = 7.97 min.
 Rainfall intensity = 4.877(In/Hr)

 Process from Point/Station 270.000 to Point/Station 270.000
 **** INITIAL AREA EVALUATION ****

Decimal fraction soil group A = 0.000
 Decimal fraction soil group B = 0.000
 Decimal fraction soil group C = 0.000
 Decimal fraction soil group D = 1.000
 [INDUSTRIAL area type]
 (General Industrial)
 Impervious value, Ai = 0.950
 Sub-Area C Value = 0.870
 Initial subarea total flow distance = 100.000(Ft.)
 Highest elevation = 537.000(Ft.)
 Lowest elevation = 535.000(Ft.)
 Elevation difference = 2.000(Ft.) Slope = 2.000 %

USER ENTRY OF INITIAL AREA TIME OF CONCENTRATION

Time of Concentration = 5.00 minutes
 Rainfall intensity (I) = 6.587(In/Hr) for a 100.0 year storm
 Effective runoff coefficient used for area (Q=KCIA) is C = 0.870
 Subarea runoff = 0.802(CFS)
 Total initial stream area = 0.140(Ac.)

 Process from Point/Station 270.000 to Point/Station 285.000
 **** CONFLUENCE OF MINOR STREAMS ****

Along Main Stream number: 1 in normal stream number 4
 Stream flow area = 0.140(Ac.)
 Runoff from this stream = 0.802(CFS)
 Time of concentration = 5.00 min.
 Rainfall intensity = 6.587(In/Hr)
 Summary of stream data:

Stream No.	Flow rate (CFS)	TC (min)	Rainfall Intensity (In/Hr)
1	51.511	10.97	3.967
2	22.091	17.87	2.897
3	5.431	7.97	4.877
4	0.802	5.00	6.587
Qmax(1) =			
	1.000 *	1.000 *	51.511) +
	1.000 *	0.614 *	22.091) +
	0.813 *	1.000 *	5.431) +
	0.602 *	1.000 *	0.802) + =
			69.978
Qmax(2) =			
	0.730 *	1.000 *	51.511) +
	1.000 *	1.000 *	22.091) +
	0.594 *	1.000 *	5.431) +
	0.440 *	1.000 *	0.802) + =
			63.280
Qmax(3) =			
	1.000 *	0.726 *	51.511) +
	1.000 *	0.446 *	22.091) +
	1.000 *	1.000 *	5.431) +
	0.740 *	1.000 *	0.802) + =
			53.273
Qmax(4) =			
	1.000 *	0.456 *	51.511) +
	1.000 *	0.280 *	22.091) +
	1.000 *	0.628 *	5.431) +
	1.000 *	1.000 *	0.802) + =
			33.863

Total of 4 streams to confluence:

Flow rates before confluence point:

51.511 22.091 5.431 0.802

Maximum flow rates at confluence using above data:

69.978 63.280 53.273 33.863

Area of streams before confluence:

17.600 21.790 1.280 0.140

Results of confluence:

Total flow rate = 69.978(CFS)

Time of concentration = 10.973 min.

Effective stream area after confluence = 40.810(Ac.)

End of computations, total study area = 40.810 (Ac.)

APPENDIX 4

Preliminary Detention Calculations

RATIONAL METHOD HYDROGRAPH PROGRAM
COPYRIGHT 1992, 2001 RICK ENGINEERING COMPANY

RUN DATE 3/20/2008

HYDROGRAPH FILE NAME S100P100.TXT

TIME OF CONCENTRATION 8 MIN.

6 HOUR RAINFALL 2.5 INCHES

BASIN AREA 19.89 ACRES

RUNOFF COEFFICIENT 0.859

PEAK DISCHARGE 80.708 CFS

TIME (MIN) = 0	DISCHARGE (CFS) = 0
TIME (MIN) = 8	DISCHARGE (CFS) = 2.6
TIME (MIN) = 16	DISCHARGE (CFS) = 2.6
TIME (MIN) = 24	DISCHARGE (CFS) = 2.7
TIME (MIN) = 32	DISCHARGE (CFS) = 2.7
TIME (MIN) = 40	DISCHARGE (CFS) = 2.8
TIME (MIN) = 48	DISCHARGE (CFS) = 2.8
TIME (MIN) = 56	DISCHARGE (CFS) = 3
TIME (MIN) = 64	DISCHARGE (CFS) = 3
TIME (MIN) = 72	DISCHARGE (CFS) = 3.1
TIME (MIN) = 80	DISCHARGE (CFS) = 3.2
TIME (MIN) = 88	DISCHARGE (CFS) = 3.3
TIME (MIN) = 96	DISCHARGE (CFS) = 3.4
TIME (MIN) = 104	DISCHARGE (CFS) = 3.6
TIME (MIN) = 112	DISCHARGE (CFS) = 3.7
TIME (MIN) = 120	DISCHARGE (CFS) = 3.9
TIME (MIN) = 128	DISCHARGE (CFS) = 4
TIME (MIN) = 136	DISCHARGE (CFS) = 4.2
TIME (MIN) = 144	DISCHARGE (CFS) = 4.3
TIME (MIN) = 152	DISCHARGE (CFS) = 4.7
TIME (MIN) = 160	DISCHARGE (CFS) = 4.8
TIME (MIN) = 168	DISCHARGE (CFS) = 5.3
TIME (MIN) = 176	DISCHARGE (CFS) = 5.5
TIME (MIN) = 184	DISCHARGE (CFS) = 6.1
TIME (MIN) = 192	DISCHARGE (CFS) = 6.5
TIME (MIN) = 200	DISCHARGE (CFS) = 7.4
TIME (MIN) = 208	DISCHARGE (CFS) = 8.1
TIME (MIN) = 216	DISCHARGE (CFS) = 9.8
TIME (MIN) = 224	DISCHARGE (CFS) = 11.2
TIME (MIN) = 232	DISCHARGE (CFS) = 16.5
TIME (MIN) = 240	DISCHARGE (CFS) = 25.6
TIME (MIN) = 248	DISCHARGE (CFS) = 80.708
TIME (MIN) = 256	DISCHARGE (CFS) = 13.2
TIME (MIN) = 264	DISCHARGE (CFS) = 8.8
TIME (MIN) = 272	DISCHARGE (CFS) = 6.9
TIME (MIN) = 280	DISCHARGE (CFS) = 5.8
TIME (MIN) = 288	DISCHARGE (CFS) = 5
TIME (MIN) = 296	DISCHARGE (CFS) = 4.5
TIME (MIN) = 304	DISCHARGE (CFS) = 4.1
TIME (MIN) = 312	DISCHARGE (CFS) = 3.7
TIME (MIN) = 320	DISCHARGE (CFS) = 3.5
TIME (MIN) = 328	DISCHARGE (CFS) = 3.3
TIME (MIN) = 336	DISCHARGE (CFS) = 3.1
TIME (MIN) = 344	DISCHARGE (CFS) = 2.9
TIME (MIN) = 352	DISCHARGE (CFS) = 2.8
TIME (MIN) = 360	DISCHARGE (CFS) = 2.6
TIME (MIN) = 368	DISCHARGE (CFS) = 0

SYSTEM 100 - COMPOSITE RUNOFF COEFFICIENT CALCULATIONS

C	A	C*A
0.87	2.78	2.419
0.87	2.62	2.279
0.87	0.81	0.705
0.87	0.85	0.740
0.87	2.53	2.201
0.82	1	0.820
0.87	0.92	0.800
0.87	1.56	1.357
0.82	1.37	1.123
0.87	0.19	0.165
0.87	1.39	1.209
0.87	1.78	1.549
0.82	2.09	1.714
11.16	19.89	17.081

C= 0.8588

File.... P:\3315\ENGR\REPORTS\DRAIN\DETENTION\PRELIM-VOL.PPW

DETENTION
 VOLUME
 REQUIRED

≈ 1.0 AF

DETENTION STORAGE ESTIMATES -- Target Peak Outflow Rate

Return Events	Peak In (cfs)	Target (cfs)	Lower (ac-ft)	Linear (ac-ft)	Curvlinr (ac-ft)	Upper (ac-ft)	Total (ac-ft)
100	80.708	25.320	.557	.681	.978	2.802	3.541

CALCULATION TIME RANGES


Return Events	Lower		Linear		Curvilinear		Upper		Total	
	From (min)	To (min)	From (min)	To (min)	From (min)	To (min)	From (min)	To (min)	From (min)	To (min)
100	4.00	254.56	3.73	254.56	.00	254.56	.00	254.56	.00	368.00

SYSTEM 100

allowable out of detention basin

$$= 95.3 - 69.98 = \text{"BACKBONE"} - \text{"System 200"} \\ = 25.32 \text{ cfs}$$

Hydrograph
Curvilinear Est 100



S100P100
Curvilinear Est 100

APPENDIX 5
Drainage Exhibits

EXHIBIT A

Drainage Map – Developed Conditions

